

Lloyd's Register of Shipping.

23 MAY 1955

Ship's Name "SEVEN SEAS"

SIGNAL LETTERS:
Official No. H.O.M.N.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in APRIL, 1955 AT BREMERHAVEN.

1. STORM VALVE OF SUBSTANTIAL CONSTRUCTION AS PER RULE FITTED TO SHELL PLATING ON STARBOARD SIDE BETWEEN C- AND DECK FWD. AT FRAME 45/46 FOR SEWAGE PLANT NOW INSTALLED CAPABLE OF BEING CONTROLLED FROM ACCESSIBLE POSITION ABOVE THE BULKHEAD DECK UNDER SERVICE CONDITIONS AND FITTED WITH INDICATORS SHOWING WHETHER THE VALVE IS OPEN OR SHUT. DRAIN PIPE FROM PUMP TO STORM VALVE 3" DIAMR OF STEEL SUBSTANTIALLY CONSTRUCTED AND GALVANIZED.

Bremen, the 2nd of May, 1955
O. H. Cooley