


Classed

(LLOYD'S REGISTER.)

VESSELS OF 100 TONS AND UPWARDS.



These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of Shipping. Signal Letters (if any) V.D.T.G.

|                             |                                    |  |
|-----------------------------|------------------------------------|--|
| Official Number.<br>174,164 | Name of Ship.<br>GREEN GABLES PARK | No., Date, and Port of Registry.<br>16-1943 Montreal, Que. |
|-----------------------------|------------------------------------|--|

No., Date, and Port of Previous Registry (if any). First Registry.

|  |  |  |   |  |
|--|--|--|---|--|
| Whether British or Foreign Built.<br>British   | Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.<br>Steam Screw  | Where Built.<br>North Vancouver, B.C.                  | When Built.<br>1943   | Name and Address of Builders.<br>North Van Ship Repairs Limited, North Vancouver, B.C.             |
| Number of Decks ... .. Two   | Number of Masts ... .. Two   | Rigged ... .. Not                                      | Stern ... .. Cruiser  | Build ... .. In & Out  |
| Galleries ... .. None  | Head ... .. Raked  | Framework and description of vessel ... .. Steel Cargo | Number of Bulkheads ... .. Seven                              | Number of water ballast tanks, and their capacity in tons ... .. 10<br>1365                        |
| Length from fore part of stem, under the bowsprit, to the fore side of the head of the stern post ... .. | Length at quarter of depth from top of weather deck at side amidships to bottom of keel ... .. | Main breadth to outside of plank ... ..                | Depth in hold from tonnage deck to ceiling at midships ... .. | Depth in hold from upper deck to ceiling at midships in the case of three decks and upwards ... .. |
| Feet.<br>424   | Feet.<br>429   | Feet.<br>57  | Feet.<br>34   | Feet.<br>-   |
| Tenths.<br>6   | Tenths.<br>-   | Tenths.<br>2   | Tenths.<br>9  | Tenths.<br>-   |
| Depth from top of beam amidships to top of keel ... ..   | Depth from top of deck at side amidships to bottom of keel ... ..                              | Round of beam ... ..                                   | Length of engine room, if any ... ..                          | Feet.<br>38<br>37<br>1<br>50   |
| Feet.<br>-   | Feet.<br>-   | Feet.<br>-   | Feet.<br>-  | Tenths.<br>5<br>2<br>-   |

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel ... 14,400 Tons. Ditto per inch immersion at same depth ... 48.5 Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

| No. of sets of Engines. | Description of Engines.  | Whether British or Foreign Made. | When made.       | Name and address of makers.                              | Reciprocating Engines.<br>No. and Diameter of Cylinders in each set. | Length of Stroke. | Rotary Engines.<br>No. of Cylinders in each set. | N. H. P.<br>B. H. P.<br>I. H. P.<br>Speed of Ship. |
|-------------------------|--|----------------------------------|------------------|--|--|-------------------|--|--|
| One                     | Triple Expansion   | Engines.<br>British              | Engines.<br>1943 | Engines.<br>Dominion Engineering Co. Ltd., Lachine, Que. | Three<br>24 1/2"<br>37"<br>70"                                       | 48"               | -  | 229 N.H.P.<br>2500 I.H.P.<br>10 knots.             |
| No. of Shafts.          | Particulars of Boilers.  | Boilers.                         | Boilers.         | Boilers.   |  |                   |  |  |
| One                     | Description: Scotch<br>Number: Three<br>Iron or Steel: Steel<br>Loaded Pressure: 220 # | British                          | 1943             | Dominion Bridge Co. Ltd., Vancouver, B.C.                |  |                   |  |  |


PARTICULARS OF TONNAGE.

| GROSS TONNAGE.   |         | No. of Tons. | DEDUCTIONS ALLOWED.   |  | No. of Tons. |
|--|---------|--------------|---|--|--------------|
| Under Tonnage Deck ... ..  |         | 6703.50      | On account of space required for propelling power   |  | 2282.20      |
| Space or spaces between Decks ... ..   |         |              | On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew    |  | 385.25       |
| Turret or Trunk ... ..   |         | 10.50        | These spaces are the following, viz. :-<br>Deck Houses ... .. 234.23<br>Tween Deck Aft ... .. 151.02<br>(Number of Seamen or Apprentices for whom accommodation is certified ... .. 58) |  |              |
| Forecastle ... ..  |         |              | Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows :-  |  |              |
| Bridge space ... ..  |         |              | Master's Accom. ... .. 21.68  |  |              |
| Poop or Break ... ..   |         |              | Chart Room ... .. 12.00   |  |              |
| Side Houses ... ..   | 84.49   |              | Wireless Inst. ... .. 7.34  |  | 219.11       |
| Deck Houses ... ..   | 214.58  |              | Steering Gear ... .. 13.63  |  |              |
| Chart House ... ..   | 12.00   |              | Bosuns Store ... .. 11.32   |  |              |
| Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ... .. | 60.06   |              | Peak Tanks ... .. 93.14   |  |              |
| Excess of Hatchways ... ..   | 46.76   |              | Total ... ..  |  |              |
| Gross Tonnage ... ..   | 7131.89 | 20183.25     |   |  |              |
| Deductions, as per Contra Register Tonnage ... ..  | 2886.56 | 8168.97      |   |  |              |
|  | 4245.33 | 12014.28     |   |  | 2886.56      |

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 867.10 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 98.10 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage. Wheelhouse 11.40 tons, Galley 12.75 tons, Light & Air (Skylight) 38.04 tons, Crew W.C.'s. 7.46 tons, (Funnel Casings)

|   |   |             |                    |
|---|---|-------------|--------------------|
| Name of Master  | Certificate of  | Service No. | No. Competency No. |
| No. of Owners   | Name, Residence, and Description of Managing Owner if there are more owners than one. |             |                    |
| His Majesty the King, in right of Canada, represented by the Honourable the Minister of Munitions and Supply, of the Dominion of Canada for the time being Ottawa, Ont.,<br>Sixty-four (64) shares. |   |             |                    |
| Park Steamship Company, Limited, of Montreal, Que., designated MANAGERS.  |   |             |                    |
| Dated Montreal, Que., June, 17th, 1943.   |   |             |                    |



012817-012835-0098