

Lloyd's Register of Shipping

2/3, Piazza Cavour

Genoa, 24th February 1948

Ref: S

Dear Sir,

RECEIVED

- 1 MAR 1948

ANSD.....

M.V. " ARTEDE "

With reference to your letter of the 21st ult. respecting Genoa Report No. 16566 on the above Vessel, we beg to offer the following remarks regarding the Hull:

- 1) The transverse Bulkheads extending over the full width and depth of the Vessel are really 8 (in our Report we reported also the Bulkheads of the centre tanks not extending to the Ship's sides.) ✓
- 2) The spacing of the rivets of the lugs to the Shell of the Side and Bottom transverses shown on midship Section is that of the flange to the webplates; the spacing of the rivets of the flange to the shell plating was checked on board and found somewhat irregular, the maximum spacing being 110 mm.
- 3) The Pump Room, the plating under the sidelights and Chain Locker were examined and found satisfactory. ✓
- 4) The spacing of the rivets in the bottom longitudinals is 99 mm. ($4\frac{1}{2}$ diameter) for 9 rivets on each side of the transverses and bulkheads, whilst the number of the rivets in the brackets the Bulkheads is 12 as reported.
- 5) The A x D numeral for the Rudder is 1266 in metric units. ✓


The other outstanding items will be replied to with the least possible delay.

Yours faithfully

The Clerk to the
Classification Committee
London.

ATG/ag

SENIOR SURVEYOR FOR ITALY



© 2021

Lloyd's Register
Foundation

Referred to Mr. Penn

Mr

For Ship Surveyors (F. E. Rals.) to note. *[Signature]*



© 2021

Lloyd's Register
Foundation



1811/1812

SHIPPING COMPANIES

SHIPPING COMPANIES

SHIPPING COMPANIES

Gross Tonnage

Total