

## Lloyd's Register of Shipping.

Ship's Name

ELLI  
GLENPARK

Official No. 166989.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

Vessel now reverted to Open Shelter Deck, & fitted for Oil Fuel, with Deep Tank amidships. Gunners accommodation removed.

HATCHWAYS: Tonnage hatch, Shelter Deck, now opened & restored to original. Bunker hatchways p/s on shelter upper decks, sal casing top dispensed with and plated over.

Upper Deck: N<sup>o</sup> 3 cargo hatch converted to W.T. hatch 10'x18' opening, 1" coaming closed by substantial bolted steel plate. 2 trimming hatches p/s similarly converted.

2 additional W.T. access hatches to Deep Tank fitted, opening 24"x21", 6" coaming closed by bolted steel plate cover.

2 Trimming hatches N<sup>o</sup> 5 tween decks reinstated as formerly.

COMPANIONWAY: Entrance to Gunners accomm. dispensed with.

VENTS: 2 @ 15" dia to bunker tween decks dispensed with, & blanked off.  
2 @ 6" " " gunners accomm " " "

AIR PIPES: 2 @ 3" dia GN, 38" high, to Deep Tank fitted at Shelter Deck  
2 @ 4" " " 14" " " N<sup>o</sup> 6 DB " " "  
2 @ 3" " " 18" " " ER DB FW tank " " "

Air pipes closed by wood plugs & canvas covers or gauzes.

SCUPPERS & SANITARY DISCHARGES: Shelter tween deck drainage to ER DB bilges p/s now reinstated & scuppers to Hold bilges blanked off.

4 @ 2½" dia additional scuppers led from tween deck in way of settling & oil separator tanks to machinery space bilges, & fitted with drop cocks.

4 Sanitary discharges from  poop tween deck accommodation led overboard below upper deck, & fitted with screw down valves operated from poop tween decks and stern valves at ship's side.

1 scupper led overboard above upper deck from  poop tween decks (SSE), screw down N.R. type fitted direct to ship's side. Original scuppers dispensed with & blanked off. Sanitary discharges from Tonnage well dispensed with & blanked off.

Tonnage well scuppers reinstated as formerly.

SIDE LIGHTS: 5-11" dia fitted in tween decks amidships, of substantial const. with hinged

CASINGS: 2 additional openings made in ER casing in tween decks, (deadlights each 2'7" x 4'8½", 18" sill, closed by hinged steel doors operated from both sides

CLOSING APPLIANCES: Openings in Bridge aft bulkhead reinstated with closing appliances as formerly. (A copy of this Report has been placed onboard)

C. B. Madden, 4/6/47.