

**DIMENSIONS:**

LENGTH BETW. PP	L = 502'-0" = 153.01 M
BREADTH MOULDED	B = 63'-9" = 20.04 M
DEPTH MOULDED TO MAIN DECK	D = 37'-11" = 11.557 M
HEIGHT OF FORECASTLE	7'-6" = 2.285 M
BRIDGE	7'-9" = 2.360 M
POOP	7'-9" = 2.360 M

**EQUIPMENT NUMBER:**

L x (B + D) = 502 (63.75 + 37.92)	= 52042
FORECASTLE 0.75 66.75	= 372
BRIDGE 0.75 42.75	= 245
POOP 0.75 109.475	= 635
DECKHOUSES AMPS 0.5 (34.475 + 36.475)	= 293
AFT 0.5 94.275	= 354
EN = 53941	

**EQUIPMENT LETTER "A"**

**EQUIPMENT:**

- 3 BOWER ANCHORS, STOCKLESS, WEIGHT 4360 KG EACH.
- 1 STREAM ANCHOR, WEIGHT EX. STOCK 1350 KG.
- 550 M 2 1/2" STUD CHAIN CABLE EL. WELDED (FLORYT).
- 220 M 5" - 6x24 STEEL WIRE
- 240 M 5 1/2" - 6x24
- 4x185 M 2 1/2" - 6x12

**CLASS:**

LLOYD'S REGISTER \* 100A1 CARRYING PETROLEUM IN BULK.

LONGITUDINAL FRAMING.

ELECTRICALLY WELDED.

The scantlings are suitable for a summer moulded draught of about 20'-6 1/2". The minimum freeboard will, however, be determined on completion of the ship by the Regulations of the Load Line Convention.

**ALT. II FOR LONG. FRAMING**

BUILT LONGITUDINALS.

BOTTOM PLATING .76"

NOTES TO BE CLOSED IN WAY OF TRANSVERSE:

15" x 42" 5" x 647" I

2286 LONG. #9

241.3

234.0

11

18" x 42" - 6" x 757" I

DETAILS FOR CUTTING OF LONGITUDINALS

DETAILS OF SCALLOPS ADJACENT TO BULKHEADS

8" IN FORWARD .20L TO BE SUBMITTED.

MELSBORG FIRST ENTRY REPORT No. 2368.14

ÖRESUNDSVARVET AB, LANDSKRONA

14.126.

MIDSHIP SECTION.

Yard No. 126 MADELEINE

RITAD AV. T.T. 29.12.50 SKALA 1:150

KORAV


GRANER AV

600K AV


0-126-100




RECORDS DEPT  
LONDON



'MADELEINE'



midship section



© 2021

Lloyd's Register  
Foundation

013284-013242-0260