

DIMENSIONS:

| | |
|----------------------------|-----------------------|
| LENGTH BETW. P.P. | L=502'-0" = 153.01 M. |
| BREADTH MOULDED | B=65'-0" = 20.04 M. |
| DEPTH MOULDED TO MAIN DECK | D=37'-11" = 11.557 M. |
| HEIGHT OF FORECASTLE | 7'-6" = 2.280 M. |
| BRIDGE | 7'-9" = 2.360 M. |
| POOP | 7'-9" = 2.360 M. |

EQUIPMENT NUMBER:

| | |
|-----------------------------------|---------|
| L x (B+D) = 502 (65.75+37.92) | = 52042 |
| FORECASTLE 0.75 66.75 | = 372 |
| BRIDGE 0.75 42.75 | = 245 |
| POOP 0.75 42.75 | = 325 |
| DECKHOUSES AMID 0.5 (34.75+36.49) | = 253 |
| — AFT 0.5 94.275 | = 354 |
| EN | = 53941 |

EQUIPMENT LETTER 71

EQUIPMENT:

- 3 BOWER ANCHORS, STOCKLESS, WEIGHT 4360 KG EACH
- 1 STREAM ANCHOR, WEIGHT EX. STOCK 1350 KG
- 550 M. 2 1/4" STUP CHAIN CABLE EL WELDED (FLORYT)
- 220 M. 5/8" 6x24 STEEL WIRE
- 240 M. 5/8" 6x24 — — —
- 4x185 M. 2 3/4" 6x12 — — —

CLASS:

LLOYD'S REGISTER 10041 CARRYING PETROLEUM IN BULK.

LONGITUDINAL FRAMING.

ELECTRICALLY WELDED.

Ward No. 126 MADEINE

HELSINGBORG FIRST ENTRY REPORT No. 2368/1

ÖRESUNDSVARVET AB, LANDSKRONA

75 BUILT M. 126

LONGITUDINAL SECTIONS AND PLAN.

RITAPAV T.T. 1842-50 SKALA: 1:100

KORAV

GRANKAV

GODKAV

0-126-101

CORRECTED AS BUILT DIN 14.4.55. H.N.

UPPRÄTTAD ENL. LLOYD'S 25.5.51. S.B.


RECORDS DEPT.
LONDON

4

"MADELEINE"



long. section & plans - as built



© 2021

Lloyd's Register
Foundation

013284-013242-0262