

17 JAN 1958

Index No. _____
(For London Office use)

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name " COASTAL CLIFF " Official No. 158658

Port of Registry MONTREAL

This ship has been under survey at MONTREAL

on 11th January, 1957 and subsequently 195 and the following alterations to the conditions of assignment of loadlines have now been effected/~~found~~:—

Vessel lengthened by addition of one tank space new amidships.

New freeboard length 251' 0".

Forecastle raised to 9' 7½" above upper deck.

New forecastle end bulkhead plating 25". Stiffeners 3" x 2½" x 30 T.W.A.

Spaced 24" bracketed top and bottom.

Openings P & S 5' 0" x 2' 0". Sill 4' 1½". Hinged steel water tight doors screwed by toggles operated from both sides.

Two openings at 5' 0" x 2' 0". Sill 12" above trunk. ^{doors} Stored by steel W.T. doors as above.

Air pipe to Forepeak space 12" above deck. Wood plug and canvas cover fitted.

Two additional hatches fitted to new tank one Port One Starboard.

Dimensions of hatches 38" x 22½".

Thickness sides and ends 3/8".

Stiffeners None.

Hatch cover Material steel.

Thickness 3/8".

Hinged watertight joint, secured by 8 toggles.

T. Taylor
SURVEYOR TO LLOYD'S REGISTER

(T. TAYLOR)

A copy of this Report has been placed on board.



© 2021

Lloyd's Register
Foundation

013311-013321-0007