

Lloyd's Register of Shipping.

Ship's Name ESSO SOUTHAMPTON

Official No. 300795

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in TRIESTE (Report N°.14848 dd. September, 1958).

PARTICULARS OF STRUCTURES, TRUNKS CASINGS, DECKHOUSES :

The particulars of openings in forecastle bulkhead, originally reported, should be cancelled and the following inserted in lieu:

2 at 1530 X 700, height of sill 460 ✓

2 at 1490 X 1080, " " " 610 ✓

PARTICULARS OF CLOSING APPLIANCES :

The closing appliances for the above openings in forecastle bulkhead are respectively:

2 hinged steel W.T. doors, secured with clips, capable of being operated from both sides. ✓

2 portable steel plates, secured with hook bolts, not passing through bulkhead. ✓

PARTICULARS OF FIDDLEY, FUNNEL AND VENTILATOR COAMINGS, ENGINE ROOM SKYLIGHT AND OTHER OPENINGS IN MACHINERY CASING TOPS AND THEIR MEANS OF CLOSING :

The particulars of vents originally reported should be cancelled and the following inserted in lieu :

8 at 1070 mm. dia. X 7 mm. thick, height 1900 mm. fixed mushroom tops ✓

4 at 650 mm. dia. X 5 mm. thick, height 970 mm., " " " ✓

2 at 1000 mm. dia. X 7 mm. thick, height 1150 mm. " " " ✓

PARTICULARS OF VENTILATORS IN EXPOSED POSITIONS ON FREEBOARD AND SUPERSTRUCTURE DECKS:

The following table should be inserted in lieu of that originally reported.

N°. OFF	DIA.	HEIGHT	THICK.	POSITION	LEADING TO	
1	596	915	10	Focle Deck	Bosun's Store	✓
2	596	915	10	DO	Fwd. cargo space	✓
4	346	915	9.5	DO	Paint Store etc.	✓
2	445	915	10	DO	Fwd. Cargo Space	✓
2	746	915	10	DO	Fwd. Pump Room.	✓
2	445	760	10	Bridge Deck	Bridge Space	✓
2	419	1000	10	Boat Deck Amidships	Accommodation	✓
1	150	760	7.5	DO	Hospital	✓
1	518	760	9	Navig. Bridge Top	Accommodation	✓
2	300	1500	8.5	After pump Room Top	CO ₂ Room	✓
1	698	9500	12	DO	PUMP Room Aft	✓
1	698	1750	12	DO	Pump Room Aft	✓
1	542	750	8 ?	Boat Deck Aft	Bosun Space Aft	✓
1	1300	254	7 ?	Top of Deckhouse Super-imposed on Boatdeck Aft	Emergency Battery Room	✓
2	1000	325	9.5	DO	Emergency Gener. Room	✓
1	610 X 1145	2780	6 ?	DO	Emergency Gener. Room	✓
1	2400 X 460	1250	6 ?	DO	Galley	✓
2	610 X 450	1400	10	Fiddley Top	Accommodation.	✓

Efficient ventilation inlets and outlets on boat deck aft top of deckhouse superimposed on same and and top of navigation bridge.

8 DEC 1958

Index No.

SHEET 2/.

Lloyd's Register of Shipping.

" ESSO JAMAICA "

Ship's Name "ESSO SOUTHAMPTON"

Official No. 300795

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in TRIESTE (Report N°.14848 dd. September, 1958)

PARTICULARS OF AIR PIPES IN EXPOSED POSITIONS ON FREEBOARD RAISED QUARTER OR SUPERSTRUCTURE DECKS:

The following table should be inserted in lieu of that originally reported:

N. OFF	POSITION	DIA.	HEIGHT	LEADING TO	
1	Focle Deck	250	460	F.P. Tank	✓
2	DO	200	460	Fwd. of Bunker	✓
2	Upper Deck	200	1640 +	DO	✓
2	DO	125	915	Fwd. cofferdam	✓
2	DO	125	915	Aft Cofferdam	✓
2	DO	200	2440 +	Aft O.F. bunkers	✓
2	DO	200	2440 +	O.F. Settling Tanks	✓
3	DO	200	915	W.B. Tanks Amidships	
2	Bridge Deck	80	800	F.W. Tanks in Bridge Space	✓
1	Poop Deck	150	460	Aft Peak Tank	✓
4	DO	65	460	D.B. Cofferdam	✓
2	Top of Deckhouse superimposed on after boatdeck.	65	460	Drinking Water Tanks	✓


+ Efficiently supported.

PARTICULARS OF ANY SPECIAL FEATURES :

On Boat deck aft 1 hatch to provision room 1830 X 1830 mm., Sill 140 X 7 mm. fitted with steel W.T. cover secured with 12 toggles. ✓

Trieste 5th December, 1958

Antin
SURVEYOR TO LLOYD'S REGISTER
OF SHIPPING - TRIESTE



© 2021

Lloyd's Register
Foundation