



STEM $6 \times 6 \times 3/8$ ANGLE
STERNPOST $6 \times 1 3/4$ "
RUDDER STOCK $4 1/2$ " DIA

EQUIPMENT

- 2- 1000 LBS STOCKLESS ANCHORS [BOWERS]
1- 336 LBS. ANCHOR [EX STOCK] [STREAM]
165 FATHOMS 1" STUD LINK CHAIN CABLE
90 FATHOMS 5/2" G. HEMP HAWSER
45 FATHOMS 2 1/2" C. FSW [STREAM WIRE]
75 FATHOMS 2 1/2" C. FSW [TOWLINE]

DIMENSIONS

LENGTH B.P.	156'-0"
BREADTH AT DK	32'-0"
BREADTH AT BOTTOM	24'-0"
DEPTH MID.	11'-9"
DRAFT MAX.	10'-0" [APPROX.]

LLOYDS, CLASSHOOD.1 FOR SERVICE ON RIVER ST. LAWRENCE
AND TO WEST END OF ANTICOSTI ISLAND.

GEO. T. DAVIE & SONS LTD.

HULL N° 34

MIDSHIP SECTION

Job No. 34-1 $\frac{1}{2}$ INCH = 1 FOOT 34.18

