

Rpt. C. 11 (Contd.)

Index No.

Lloyd's Register of Shipping.

Ship's Name "KOS 1"

SIGNAL LETTERS

Official No. L.D.K.T.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in FEBRUARY 1952.

THE FOLLOWING ITEMS DEALT WITH AT THIS TIME IN ACCORDANCE WITH THE SECRETARY'S LETTER OF 15TH FEBRUARY 1952. -


- ① FORWARD COMPANIONWAY SILL INCREASED TO 24" IN HEIGHT ABOVE DECK
- ② DEADLIGHTS SUPPLIED TO PORTLIGHTS IN SKYLIGHTS.
- ③ VENTILATORS OVER 3'0" IN HEIGHT ADEQUATELY STIFFENED OR IN PROTECTED POSITION.
- ④ WIRE GUARD RAILS FITTED WITH GALVANISED STRETCHING SCREWS.

TO PROVIDE VENTILATION TO A DOMESTIC REFRIGERATOR IN THE HOLD SPACE A 7" DIA. COWL VENTILATOR FITTED ON TOP OF STEEL HATCH COVER. VENT COAMING 3/4" THICK 17" ABOVE HATCH TOP. WOOD PLUG & CANVAS COVER SUPPLIED.

B. J. Witowski /

A COPY OF THE ABOVE REPORT PLACED ON BOARD THE SHIP.

Noted on Rpt C11.



14 APR 1952



© 2021

Lloyd's Register
Foundation