

27 NOV 1955

34848

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

Ship's Name "SWANHILL"

Official No. 164093

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

Hatchways fitted on Superstructure and Freeboard decks to provide access to hold ladders clear of the main hatchways.

On the Superstructure Deck:- Four (4) hatchways fitted in the 3rd beam space from the forward or after end of the Nos. 1, 2, 4 & 5 main hatchways at the centre line of the ship. Size of Opening 24" x 24", Coaming $\frac{1}{2}$ " plate, 24" high.

Wood covers on 3" rests, Cleats spaced 12", 2 tarpaulins.

On the Freeboard deck:- Four (4) hatchways fitted adjacent to the bulkhead in the Nos. 1, 2, 4 & 5 Lower Hold at the centre line of the ship.

Size of Opening 24" x 24", Coaming 9 x $3\frac{1}{2}$ x 7/16" B.A.

Wood covers on 3" rests, Cleats spaced 12", 1 Tarpaulin.

W.B. Eden

Surveyor to Lloyd's Register

Newcastle N.S.W.

8th November, 1955.

WPR

23 NOV 1955

013651-013655-0300

Original Rpt C.11 (Contd.) placed on Board

Fee 20-0-0

32 10-0-



© 2021

Lloyd's Register
Foundation