

25 DEC 1941

Lloyd's Register of Shipping.

34848

Ship's Name M.V. "QUEEN ADELAIDE"

Official No. 164093

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

In compliance with the instructions of the Ministry of War Transport re: closing of shelter decks the following alterations have been carried out:-

The tonnage hatchway has been raised to 30 inches - fitted on top with a steel booby hatch 2'-10" x 5'-3" - remainder of hatchway closed by hatchboards and tarpaulins - The port side opening in the tonnage space bulkhead has been plated up while the starboard side remains for access to extra gunners accommodation. The tonnage space, crew and steering gear spaces drained to tunnel well -

Washports in tonnage space welded up.

All overside scuppers have been spigot-patched and drain scuppers at these points led to the bilges.

Arrangements have been made for the rigging of lifelines.

The bulkheads are not continued to shelter deck.

ERECTIONS:- Forecastle 35'-0" long - one opening, closed by storm-boards to full height.

New freeboards as assigned by London cablegram dated 26.8.41.

Tropical Fresh Water 9 ft. 11 $\frac{1}{2}$ ins.

Fresh Water 10 " 6 $\frac{1}{2}$ "

Tropical 10 " 6 $\frac{1}{2}$ "

Summer 11 " 1 $\frac{1}{2}$ "

Winter 11 " 8 $\frac{1}{4}$ "

CALCUTTA.

2.9.41.

Ice Rs. 60/-

Noted
10/12/41