

Fld. 2166.

# Lloyd's Register of Shipping. 29 JUL 1944

Ship's Name "QUEEN ADELAIDE"

Official No. 164093

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

The following alterations have now been carried out and found satisfactory.

New ventilators fitted on upper deck amidships 2 port and 2 starboard, leading to tween deck spaces abreast machinery spaces; substantial coamings 8" dia. and 24" high, with wood plugs and canvas covers. ✓

One new ventilator fitted near companionway on after deck, leading to after store space. Substantial coaming 8" dia., 24" high, with wood plug and canvas cover. ✓

One additional sidelight fitted in way of new accommodation in port after tween decks; 10" dia. with hinged C.I. deadlight. ✓

*A.M.B. Edwards*

Surveyor to

Lloyd's Register of Shipping

*Hull 22/7/44*

Steel W.T. bulkheads have been fitted in the shelter decks, at frames 37, 60, 77 and 128. This work has been carried out on the instructions and under the supervision of the local M.W.T. Surveyors. Steel plates 5/16", part riveted and part E.W. Stiffeners 6" x 3" x 1/2" bulb angles at approx. 33" pitch; no brackets. The bulkhead ford of the machinery spaces has been fitted with hinged W.T. doors P. & S. Suitable scuppers have been fitted P. & S. in all the enclosed 'tween deck spaces, draining to the hold bilges.

*A.M.B.*

*Noted.*

*29 JUL 1944*  
*J.P.*



© 2021

Lloyd's Register  
Foundation