

It is submitted a copy of the report be forwarded to the Cadiz Surveyors for their information.

Regarding the attached test result sheet for air receivers made by Brunon & Valette at Rive-de-Gier (Loire) it is submitted the steel testing Surveyor at St. Etienne be requested to state whether it is to be understood that only 4 of the 8 receivers had the material tested for tensile strength and that the material for the other 4 receivers was subjected to bend tests only.

If this is the case his attention should be drawn to Par. 5 Sec.6 of the Rules for Heavy Oil Engines and their Auxiliaries, page 133 of the current issue, from which it will be seen that tensile and bend tests are to be made from the material of each receiver.

The Surveyor should also state the internal diameter and thickness of each receiver, whether they have been tested by water as required by the Rules and whether the receivers are solid drawn or lap welded.

L Am 16/9/33

25th 15/9/33



© 2021

Lloyd's Register
Foundation