

3m, 6, 49.

Scheepswerven Gebr. Van Diepen N.V.Yard No. 918

Received by Chief Ship Surveyor

Received from Chief Ship Surveyor

VESSEL'S NAME Sin. Sc. Motorship "ZAMRUD"

REPORT

Gro.

No. 677

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/92.)

Framing .. As approved.

Sheerstrake .. As approved.

L. 160.09' B. 30.02' D. 9.33' to Upper Dk. Proportions 10.2
15.75' to Sh. Dk.

The stream anchor is reported as 3cwts 2qr 1.1b instead of 4 cwts 1 qr. as required by the Rules, it is therefore submitted the Figure '1' be assigned, subject to a stream anchor of Rule weight being supplied.

The scantlings and arrangements, as reported, conform with the Society's Revised Rules and Regulations, and are in accordance with or equivalent to those shown on the approved plans.

It is therefore submitted the ship is eligible to be
classified -100A1 }
5,52 Dzl. } Subject1 Dk & Shelter Dk. "pt Elec. welded"
Cell DB-103' pt W.B. 95t pt O.F.; FFT 13t; APT 19t.
FK, 4BH (3 to Sh dk, 1 to 2nd dk), Lloyd's A & CP, pt Asp.
P 40' B 31' F 21'
Mohy Aft
O.L. 179.2'
ESD
"1"REVISED CERTIFICATE
C.S.S. Records Dept.

to note.

(Increased length of cables).

It is further submitted the Surveyor be advised it is concluded the length of the bridge is 31' as measured on the approved plan and not as stated in the report, but this should be confirmed.

It is also concluded bitumastic is only fitted in the water ballast tanks and not in the oil fuel tanks.

S.R. LIST

Stream anchor (supplied 5,52) to be replaced by one of correct weight as soon as possible.



© 2021

Lloyd's Register
Foundation

013783 - 013793 - 0250

" " Are Frame and Reversed Frame }
joggled?

no

✓

Spacing