

G.R. 130.

(LLOYD'S REGISTER.)**VESSELS OF 100 TONS AND UPWARDS.**

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of Shipping.

Signal Letters (if any).....



Official Number.	Name of Ship.	No., Date, and Port of Registry.	
168464	C. 614	142 in 1943 London.	
No., Date, and Port of previous Registry (if any).			
Whether British or Foreign Built.	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.
British	Steam Ship Single Screw	Northwich	1943
		Name and Address of Builders.	
		W.J. Yarwood & Sons (1938) Limited, Northwich.	
Number of Decks	One & Raised Quarter Deck	Length from fore part of stem, to the aft side of the head of the stern post	Feet. 127
Number of Masts	One	Main breadth to outside of plank	24
Rigged	Not	Depth in hold from tonnage deck to ceiling amidships	9
Stem	Straight	Depth in hold from upper deck to ceiling amidships, in the case of three decks and upwards	-
Stern	Cruiser	Depth from top of deck at side amidships to bottom of keel	-
Build	Clencher	Round of beam	36
Framework and description of vessel	Steel-Cargo	Length of engine room, if any	7.5
Number of Bulkheads	Four		

Particulars of propelling Engines, etc. (if any), and Water Ballast Tanks, as supplied by Builders, Owners, or Engine Makers.

No. of sets of Engines	Description of Engines	Whether British or Foreign Made	When made	Name and address of makers	Reciprocating Engines		Rotary Engines		N.H.P. B.H.P. L.H.P. Estimated Speed of Ship
					No. and Diameter of Cylinders in each set	Length of Stroke	No. of Cylinders in each set		
One	Triple Expansion, Vertical	Engines British	Engines 1943	Engines W.J. Yarwood & Sons, (1938) Limited, Northwich.	Three 10 $\frac{1}{2}$ " 17 $\frac{1}{2}$ " 29"	19"	-		60 320 385
One	Particulars of Boilers								8 knots
	Description	Return Tube							
	Number	One	Boilers	Boilers					
	Iron or Steel	Steel							
	Loaded Pressure	200 lbs.	British	1943	Cammell Laird & Co., Ltd., Birkenhead.				

Number of water ballast tanks, and their capacity in tons:— Two - 62 tons.

013890 - 013899 - 0052

(P.T.O.)

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck	252.25	On account of space required for propelling power	110.80
Space or spaces between Decks		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from Goods or Stores of every kind not being the personal property of the Crew.	
Turret or Trunk	16.73		
Forecastle			63.15
Bridge space			
Poop or Break	53.77	These spaces are the following, viz.:—	
Side Houses		In Poop, Forecastle and Round House	
Deck Houses	11.80	(Number of Seamen or Apprentices for whom accommodation is certified.....12.....).	
Chart House			
Spaces for Machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894		Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
Excess of Hatchways	11.71		
		Cubic Meters.	
Gross Tonnage	346.26	Master's Accommodation 4.78)	
Deductions, as per contra	206.11	Boatswain's Store 6.93)	32.16
		Water Ballast Spaces 20.45)	
Register Tonnage	140.15	Total	206.11

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 53.78 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 18.24 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

None

Name of Master	Certificate of { Service No. Competency No.
No. of Owners	The Secretary of the Admiralty, Whitehall, S.W.1., designated
Name, Residence, and Description of Managing Owner if there are more owners than one.	Managing Owner, under Order in Council 22nd March, 1911.
HIS MAJESTY represented by the Commissioners for executing the Office of Lord High Admiral of the United Kingdom, London. Sixty-Four Shares.	
Dated 24th June, 1943.	

Registrar.

Lloyd's Register
Foundation