

Rpt. 8

REPORT OF SHIP SURVEYS AND REPAIRS

Received London

27 SEP 1965

Ship's Name ~~SS/MS~~ Steam Tug "HIMMA" 274 Gross tons of Sydney.
LR - 515088
Is there a rpt. 9? Yes Port SYDNEY, N.S.W. Rpt. No. 38124
No. of visits 4 First date 2nd July Last date 4th Aug., 1965.
Interim Cert. issued & copy herewith? Yes Damage rpt. issued & copy herewith? No Last rpt. (H.Q. only) SYD 37208
Date of completing rpt. 13. 9. 65 Surveyed at, if different from Port above -
Surveyed afloat and/or in D.D. Both Last date of examination in D.D. 27th July, 1965.
Has a Load Line Survey been held? Yes Freeboard Marks verified YES

State which additional Rpt. 8 is attached: (Cont); (PS); (DR); (EQ); (Rig) P.S.

Survey fees	Damage fee	Expenses
£88. 0. 0	NIL.	10/-
		S.A. fee NIL.

I have surveyed the above ship in accordance with the Rules for SPECIAL SURVEY (C') due 7,64

WEAR AND TEAR REPAIRS.

The items now surveyed are detailed on this report. All were found or placed in good condition unless otherwise stated.

WEAR & TEAR REPAIRS:

Now Done: One doubler plate welded to shell p. s. of E.R. where water dripping from engine driven bilge pump had caused local wastage in shell.

About 8 feet of deck plating alongside E.R. skylight casing p.s. part cropped and renewed.

Deckhouse plating p.s. in way of steampipes part cropped up 18" and renewed.

Both latter repairs hose tested on completion and found satisfactory. Sundry minor repairs carried out.

S.R.L. APPENDIX No.16:

Indents in sheerstrake and strake below (p & s) examined and considered no action required. The plates remain efficient.

I recommend that this ship remain as classed with/~~without~~ fresh record of dry docking 7,65 and notation of S.S. 8,65 without special condition.

(Where conditions of class are recommended to be retained, imposed, amended or deleted, particulars must be stated above and on the interim certificate)

Date of Committee

Minute

THURSDAY 21 OCT 1965

Surveyor to Lloyd's Register of Shipping

A. J. DIX, J. H. JAMIESON, - & P.H.W. EVANS

FOR CHAIRMAN
CLASSN. CTTEE

ALSO FOR

NOTED BY
SPL FOR
C.S.S.
RECORDS
TWO DEPT.

SRL

POSTING

HEADER

CERT

21 OCT 1965

action taken or recommended should be described fully under "defects & repairs". When any part has been subjected to pressure test this should be stated.

date of the next Special Survey. Where repairs have been effected or it is considered that re-examination or repairs should be made before that date the circumstances and

The condition of any item is to be described as "good" only when it has been examined, found or placed in good condition and is considered to be acceptable until the due