

COPY. *for London*

18 AUG 1933

Lloyd's Register of Shipping.



Port of Cadiz.

April, 24th. 1933.

Ped. 2892/11.064.

O.P.1.718.

This is to Certify that

I. Robert A. Black.

the undersigned Surveyor to this Society did at the request of Messrs. Constructora Nacional Maquinaria Electrica of Cordoba, attend at their works on the 20th. of April and subsequent dates for the purpose of testing and witnessing the final shop trials of two Generators Nos. 752 & 753 as specified below to the order of Messrs. Sociedad Española de Construcción Naval Bilbao. Makers Type S.R. 250 - 220 Volts 318 Amps output 70 K.W. Speed 375 Revs.

The Generators were submitted to a trial of 6 hours consecutively under full load and 25% overload. The maximum temperatures were found to be within the requirements called for in the British standard specification No 168 On completion of the full and overload tests the insulation was tested to 2000 volts with satisfactory results.

For identification the Generators have been stamped:-

Lloyds Test.
24/4/33.
RAB No 1 & 2.

R. Black

Acting Surveyor to Lloyds Register.

M. V. Campeche

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:-

"While the Committee use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Committee nor the Society are under any circumstances whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default, or negligence of the Surveyors, or other Officers or Agents of the Society."