



s.s."THORA DAN" ex "HOKE SMITH".

R.B. No.75204 - Electrical Installation

IT IS SUBMITTED the Copenhagen Surveyors
be informed that in compliance with the requirements
of Section 6, Clause 7 the equaliser connections are
to be at least half the sectional area of the generator
mains. The existing mains on this vessel ^{are} ~~was~~ 37/.082,
nominal cross-sectional area 0.1969 sq.inches, and a
suitable cable, rubber insulated, would be **19/.083** or
its metric equivalent.


9.5.47




© 2021

Lloyd's Register
Foundation

014364-014371-011