

TANK CAPACITIES IN TONS					
COMPARTMENT	LOCATION FR. NOS	WATER BALLAST 36 C.F.T/TON	FRESH WATER 36 C.F.T/TON	DOMESTIC FRESH WATER 36 C.F.T/TON	OIL FUEL 42.7 C.F.T/TON
No 1 TANK CR. LINE	0-6	—	—	31.6	—
No 2 TANK P.S.	0-6	40.40	—	—	—
No 3 TANK CR. LINE	11-13	—	7.00	—	—
No 4 TANK P.S.	11-16	—	—	28.20	—
No 5A TANK P.S.	30-37	—	—	—	49.40
No 5B TANK P.S.	37-45	—	—	—	56.40
No 6 TANK P.S.	46-52	—	51.40	—	—
No 7 TANK P.S.	85-96	80.60	—	—	—
TOTALS		121.00	58.40	59.80	105.80

NOTE: WATER TANK CAPACITIES 100% FULL OIL TANK CAPACITIES 95% FULL.

STORES ETC.	WEIGHT IN TONS	V.C.G. ABOVE MID. BASE	L.C.G. FROM MIDSHIPS AFT	FOR ^D
CREW-EFFECTS & STORES	20.00	12.00	—	—


N.P. BUCKET DREDGER.

"STEENBOK"

CAPACITIES & CENTRES OF GRAVITY.


SCALE:- 1/16" = 1'-0".



"STEENBOK" 
FERGUSON BROTHERS LTD.
YARD No. 443.
CAPACITY PLAN.

GREENOCK F.E. REPORT No. 27804

RECORDS DEPT.
LONDON.



© 2021

Lloyd's Register
Foundation

014501-014512-0293