



all welding to be in accordance with Table 52 of the Rules and to be to Surveyors satisfaction

		RIVETING NIETUNG		WELDING SCHWEISSUNG	
bilge keel	with shellplating	Schlingerkiel	mit	Aussenhaut	3 durchl.
floor plate	keelplate	Bodenwange		Kielplatte	4 "
"	shellplating	"		Aussenhaut	3 55 / 140 A
"	girder	"		Gurt	3 45 / 140 Z
"	keelson	"		Kielschwein	4 durchl.
"	keelplate	"	Masch.R.	Kielplatte	5 "
"	shellplating	"		Aussenhaut	3,5 55 / 140 A
"	girder	"		Gurt	3,5 60 / 170 Z
"	Engine foundation	"		Motorfundament	5 durchl.
Bulkheads	shellplating	Schotte		Aussenhaut	3 "
"	stiffeners	"		Stößen	3 45 / 140 Z
"	main deck	"		Hauptdeck	3 durchl.
Side frame	floorplate	Seitenst.		Bodenwange	4 "
"	shellplating	"		Aussenhaut	3,5 60 / 170 Z
"	bracket	"		Deck-Kniebl.	3 durchl.
web frame	shellplating	Rahmenspl.		Seite Aussenh.	3,5 60 / 170 A
deck beam	main deck	Deckbalken		Hauptdeck	3 45 / 140 Z
"	bracket	"		Deck-Kniebl.	3 durchl.
"	deck girder	"		Unterzug	3 "
"	web frame	"	Rspl.	Hauptdeck	3,5 60 / 170 Z
"	girder	"		Gurt	3,5 60 / 170 Z
"	deck girder	"		Unterzug	3,5 durchl.
main deck	sheer strake	Hauptdeck		Schergang	5 "
"	coaming	"		Aufbau stüll	3 "
waterway coaming	deck stringer	Rinnstein stüll		Deckstringer	3,5 "
Al longitud. walls	coaming	Al Längswand		Stüll (auf Deck)	Al 10 d, 5 d
Al cross walls	"	Al Quersw.		"	" " 8 d
Al longitud. walls	stiffeners	Al Längsw.		Stößen	" " 8 d
Al cross walls	"	Al Quersw.		"	" " 8 d
top angle	walls	Top Winkel		Wänden	" " "
deck beam	bridge deck	Deckbalken		Brücken deck	3 45 / 140 Z
"	wall stiffeners	"		Wandstößen	3 durchl.
"	bracket (facepl.)	"		Kniebl. (facepl.)	3 "
faceplate	bridge deck	Faceplatte		Brückendeck	5 "
"	girder angle	"		Gurtwinkel	Al 10 d, 5 d
"	stanchions	"		Stützen	ver. 8 d, 3 d
deck beam	cross walls	Deckbalken		Querwände	Al 10 d, 5 d
bridge deck	coaming	Brückendeck		Aufb. Stüll	" " 5 d
walls	"	Wände		"	" " 5 d
"	stiffeners	"		Stößen	" " 8 d
"	deck head	"		Decke	" " 5 d
stiffeners	bracket	Stößen		Deck-Kniebl.	3 durchl.
deck beam	"	Deckbalken		"	3 "
"	deck head	"		Decke	3 45 / 140 Z
"	girder	"		Unterzug	3 durchl.
deck head	"	Decke		"	3 45 / 140 Z

CLASS LR A/1 "FOR RESTRICTED SERVICE"

- ANCHORS AND ROPES**
- 1 (2) BOWER ANCHORS 4 1/2 cwt.
 - 45 (60) fathoms CHAIN CABLE 3/16"
 - 60 " MANILA ROPE 5"
 - 60 " " 3"
 - 60 " " 5 1/2"
 - 60 " TOW ROPE ON PULLEY, 5 1/2"

ALL ROPES WITH EYE-SPLICE ON EACH END.

L B P = 26.0 M
 Breadth = 6.1 M
 Depth = 2.74 M

London Copy

N. 1452
FEUERLO'SCHBOOT
PROPOSED TRIPLE SCREW
MOTOR FIRE FLOAT
 Propulsion 3 x 115 WPS

014556-014565-0057

MIDSHIP SECTION

①

YARD NO. 1452

CHRISTOP ROTHOF G.B.H.

RETAIN IN RECORDS

NO TRACE?



© 2021

Lloyd's Register
Foundation