

G.R. 130

(LLOYD'S REGISTER)

VESSELS OF 100 TONS AND UPWARDS

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of Shipping.

Signal Letters (if any) **V C N R**

Official Number.	Name of Ship.	No., Date, and Port of Registry.
176, 107 017	RUPERT PARK	16-1945 Montreal, Que.

No., Date, and Port of Previous Registry (if any). First Registry

Whether British or Foreign Built	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steam Screw	North Vancouver B.C.	1945	Burrard Dry Dock Co. Ltd., North Vancouver, B.C.

Number of Decks Two	Length from fore part of stem, under the bowsprit, to the fore side of the head of the stern-post or rudder stock ...	Feet	Tenths
Number of Masts Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ...	424	6
Rigged Stem Not Raked	Main breadth to outside of plank ...	57	2
Stern Cruiser	Depth in hold from tonnage deck to ceiling at midships	34	9
Build In & Out	Depth in hold from upper deck to ceiling at midships in the case of three decks and upwards ...	-	-
Galleries	Depth from top of beam amidships to top of keel ...	37	5
Head	Round of beam ...	1	2
Framework and description of vessel Steel Cargo	Length of engine room, if any ...	50	-
Number of Bulkheads Seven			
Number of water ballast tanks and their capacity in tons ... TWELVE - 1352 tons			

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel ...	Tons.	Ditto per inch immersion at same depth ...	Tons.
--	-------	--	-------

PARTICULARS OF PROPELLING ENGINES, Etc. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign Made.	When made.	Name and address of makers.	Reciprocating Engines. No. and Diameter of Cylinders in each set.	Length of Stroke.	Rotary Engines. No. of Cylinders in each set.	N. H. P. B. H. P. I. H. P. Speed of Ship.
ONE	Reciprocating Triple Expansion	Engines. British	Engines. 1945	Engines. Dominion Engineering Works Ltd. Lachine, Que. Boilers.	THREE 24 1/2"	48"		N.H.P. 229
No. of Shafts.	Particulars of oilers. Description Number Three Steel	Boilers. British	Boilers. 1945	Boilers. Dominion Bridge Co. Ltd., Vancouver, B.C.	37"	70"		I.H.P. 2500 Speed 11 Knots
ONE	Iron or Steel. Loaded Pressure 220 #							

014604-014618-0321

Lloyd's Register Foundation

PARTICULARS OF TONNAGE.

GROSS TONNAGE	No. of Tons	DEDUCTIONS ALLOWED.	No. of Tons
Under Tonnage Deck	6704.46	On account of space required for propelling power	2287.26
Space or spaces between Decks		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew ...	
Turret or Trunk	10.50	These spaces are the following, viz. :—	
Forecastle		Deckhouses,	422.82
Bridge space		(Number of Seamen or Apprentices for whom accommodation is certified 66)	
Poop or Break	79.37	Deductions under Section 79-94 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
Side Houses	225.09	Master 22.72	
Deck Houses	11.28	Chart Room 11.28	
Chart House		W.T. Rooms 7.59	
Spaces for machinery, and light, and air, under Section 53-93 of the Merchant Shipping Act, 1894, 1934	61.00	Steering Gear 16.64	
Excess of Hatchways	55.98	B'wain Stores 71.48	
		Water Ballast 93.78	
Gross Tonnage	7147.68	Cubic Metres	223.48
Deductions, as per Contra	2933.57		
Register Tonnage	4214.11		2933.57

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 868.38 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 98.10 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Wheelhouse 10.01 tons, Galley 11.52 tons, Crew W.C. 8.10 tons, Companion .92 ton,

Light & Air 37.10 tons, TOTAL - 67.65 tons

Name of Master	Certificate of { Service No. Competency No.
No. of Owners	
Name, Residence, and Description of Managing Owner if there are more owners than one.	
Honourable the Minister of Munitions and Supply, of the Dominion of Canada, Ottawa, Ontario. Sixty-four shares (64)	
Managers:— Park Steamship Co. Ltd., 410, St. Nicholas Street, Montreal, Que.	
Dated Montreal, Que. April, 13th 1945.	