

Lloyd's Register of Shipping.

Ship's Name JOSEPH PHILIP

Official No. 123345

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in JULY, 1932.

Sidelights to crew space forward permanently closed by riveted plates.

Four 15" diam. cast iron flush bunker scuttles on freeboard deck

dispensed with, holes in deck permanently closed by riveted plates. One

bunker hatch on each side of the vessel in lieu of these scuttles.

Hatch 4'6" x 2'4", 36" coaming, 3/8" ^{thick} ~~bars~~, rest bars 2 1/2 x 2 1/2 x 3/8, wood
covers 2 3/4" thick, with battening bars, 2 tarpaulins and cleats to each
hatch.

62