

Lloyd's Register of Shipping.
SURVEYS FOR FREEBOARD.—STEAM SHIPS.

PARTICULARS RELATING TO ALL STEAM SHIPS EITHER FLUSH DECKED, OR WITH TOP GALLANT FORECASTLES, SHORT POOPS AND BRIDGE HOUSES DISCONNECTED, OR WITH TOP GALLANT FORECASTLES HAVING LONG POOPS, OR RAISED QUARTER DECKS CONNECTED WITH BRIDGE HOUSES, OR OTHERWISE.

Port of Survey Dundee
Date of Survey 15.7.32
Name of Surveyor -

Ship's Name. Joseph Philip
Port of Registry and Nationality. Dundee British
Official Number. 123345
Gross Tonnage. 623
Date of Build. 1914
Particulars of Classification. +100 A1. Hopper Barge.

n Register Book

LENGTH.	BREADTH.	DEPTH.	UNDER DECK TONNAGE.
170.0	30.15	14.25	595.95
170.0	Frame Depth 5 Rule " 3 1/2 2 x 1 1/2 - .25 No. of stringers + .25	Ceiling + .20 Sheer + .38 Depth to Floors = 14.29	Peak Tanks ✓
170.0	30.15	14.87	595.95

Moulded Depth as measured..... 15'-0"
Wood deck less stringer - 3
14-9 Mld. Depth to use.
Addition for Keel below base line for draught record..... inches.

NOTE.—If the depth is measured when vessel is afloat, the details of measurement should be reported.

CORRECTION FOR LENGTH.

Length of Ship on Loadline..... 170
Length in Table 177
Difference 7
Correction for 10ft., Table A. 1.0 Table C.
x Difference divided by 107 (if required.)
If 1/10ths length covered divide by 2 - 3/4

CORRECTION FOR IRON DECK.

Proportion covered, if less than 1/10ths length covered
Thickness of usual wood deck, less stringer allowed in reduced moulded depth.

CORRECTION FOR ROUND OF BEAM.

Breadth at Gunwale amidships..... 30'-0"
Round of Beam 7 1/2"
Normal round..... 7 1/2"
Difference ✓ ÷ 2 =
Proportion of Deck uncovered (Para. 19) ✓

NOTE.—The round of beam should be reported on the full breadth of vessel at the gunwale.

Freeboard, Table A 2'-5 1/4"
Correction for Sheer 3/4"
2'-2"
Correction for Length 3/4"
2'-1 1/4"
Allowance for Deck Erections ✓
Correction for Round of Beam..... ✓
Correction for fall in Sheer (if any)..... ✓
Correction for Steel Deck (if required) ✓
Additions for non-compliance with provisions of Para. 11 (d) and (e) ✓
Other Corrections (if any) form of hopper + 1 3/4"
2'-3"

Winter Freeboard 2'-3"
Summer Freeboard 2'-1 1/2"
Indian Summer Freeboard
N. A. Winter Freeboard

Correction necessary because clearside amidships, measured in accordance with the Statute is not taken at the intersection of the wood or steel deck with side. N.L.

Winter Freeboard from deck line
Summer " " " "
Indian Summer " " " "
N. A. Winter " " " "

SUMMER FREEBOARD amidships from Centre of Disc to top of Deck Line, wood, Steel, Deck:—

Tropical Fresh Water Line above Centre of Disc ... 5 1/4" 5" Tropical Fresh Water Freeboard ...
Fresh Water Line " " ... 3 1/2" 3 1/2" Fresh Water " " ...
Tropical Line " " ... 1 1/2" 1 1/2" Tropical " " ...
Winter Line below " " ... 1 1/2" 1 1/2" Winter " " ...
Winter North Atlantic Line " " ... 3 1/2" 3 1/2" Winter North Atlantic " " ...

126 JUL 1932

7.10 1133 10.765 = 371-3 3/4" Fresh Water = 14.84 10.5 x 40 = 3 1/2"