

Received London
21 SEP 1964

Ship's Name ~~SS~~/MS "NAGAOSAN MARU" Gross tons 6555
 Is there a rpt. 9? Yes Port KOBE Rpt. No. 13259
 No. of visits 5 First date 14th Aug., 1964 Last date 19th Aug., 1964
 Interim Cert. issued Yes, Damage rpt. issued & copy herewith? B-106235 & copy herewith? No Last rpt. (H.Q. only) Kod. 11886
 Date of completing rpt. 22nd Aug., 1964 Surveyed at, if different from Port above Tamano
 Surveyed afloat and/or in D.D. Drydock Last date of examination in D.D. 19/8/64
 Has a Load Line Survey been held? Yes, by NK Freeboard Marks verified Yes

25 SEP 1964

State which additional Rpt. 8 is attached: (~~CS~~) (PS) / (~~PP~~) / (~~PP~~) (Rig)

Survey fees S.S. ¥174,000.- Damage fee ¥10,000.- Expenses ¥7,500.-
 S.A. fee -

action taken or recommended should be described fully under "defects & repairs". When any part has been subjected to pressure test this should be stated.

date of the next Special Survey. Where repairs have been effected or it is considered that re-examination of repairs should be made before that date the circumstances and

The condition of any item is to be described as "good" only when it has been examined, found or placed in good condition and is considered to be acceptable until the due

I have surveyed the above ship in accordance with the Rules for Special Survey 'A' due 8,64 and damage stated to have been sustained by contact with quay wall at Port Pirie on 10th January, 1964.

The items now surveyed are detailed on this report. All were found or placed in good condition unless otherwise stated.

Special Survey:

All items required for SS (A) have been carried out, please see Rpt.8(P.S.).

Defects and Repairs:

Set in F'cle side shell upper edge P. side cropped and part renewed, bent open hand rail and stanchions in way faired in place. Soundry minor repairs also effected.

Damage:

Indented side shell plate F14 (numbered from aft) P. side in way of No.2 hold cropped and part renewed, adjacent plate G15 faired in place. On completion of above repairs side shell hose tested and found tight.=


I recommend that this ship remain as classed with/without fresh record of dry docking 8,64 and to have the notation of SS 8,64.

(Where conditions of class are recommended to be retained, imposed, amended or deleted, particulars must be stated above and on the interim certificate.)

Date of Committee THURSDAY 15 OCT 1964

Minute DS 8. *law*
 SS 8. *law* CSM 8. *law*
 ABS 8. *law* SPS 8. *law*

Noguchi
 Surveyor to Lloyd's Register of Shipping
 S. Noguchi



Lloyd's Register Foundation

ALSO FOR	
SPL FOR	
TRO	
SRL	<input checked="" type="checkbox"/>
POSTING	<input checked="" type="checkbox"/>
HEADER	<input checked="" type="checkbox"/>
CERT	<input checked="" type="checkbox"/>

014784-014793-0208 1/3

19.10.64

ho

Condition of Class:

S.R.L. No.222: Nil

S.R.L. Appendix No.14: Nil

PARTICULARS OF DEFECTS, REPAIRS, ALTERATIONS, ETC. The reason for repairs must be stated and repairs on account of damage, the alleged cause of which must be given, should be detailed separately from wear and tear repairs and, besides being detailed above, should be noted in the following summary. *State what action has been taken regarding items which are subjects of class or in SRL Appendix, whether outstanding or new.* Any alterations in existing particulars in the Register Book should also be reported above.

SUMMARY OF DAMAGE REPAIRS	SHELL PLATES	FRAMES	DECK PLATES	BEAMS	OTHER ITEMS
Renewed	1 (part)				
Removed and faired or replaced	.				
Faired or repaired in place	1				



© 2021

Lloyd's Register
Foundation

Rpt. 8 (P.S.) DRY CARGO SHIP

Ship's Name ~~SS~~/MS "NAGAOSAN MARU"

S.S. (A) Due 8,64

Port KOBE

Rpt. No. 13259

	<u>Examined & condition</u>		<u>Examined & condition</u>
In dry dock from	14/8/64	* Air & sounding pipes	Good
„ „ „ to	20/8/64	Doublers under „ „	Good
Shell plating	Good	Steering arrangements (main)	Good
Sternframe	Good	„ „ (aux)	Good
Rudder	Good	Windlass	Good
Was rudder lifted?	Yes	Masts & rigging	Good
Plating, etc. in way of shell openings	Good	Hand pumps & suction	Good
Side scuttles & deadlights	Good	W.T. doors	Good
Overbd. scuppers & discharges	Good	Bulwarks, freeing ports, etc.	Good
F.P. spaces	Good		
Chain locker	Good	Summer freeboard as verified	3125 mm <i>NOT IN RB</i>
A.P. spaces	Good		<i>REPS TO NOTE</i>
Engine space	Good		<i>Noted on Fld. List-20%</i>
Boiler space	Good	<u>EQUIPMENT:</u>	
Under E. & B.	Good	Equipment letter	at 2 1/8" SQ ✓
Coal bunker	None	Fee ltr., if diff. from eqpt. ltr.	-
Tunnel & well	Good	Anchors: No. on board	3B
Cement, asphalt, etc., on btm. shell	Good		
Weather decks	Good	Cables { State if ranged	Yes
* Casings	Good	Length on board	275 fms
* Deckhouses	Good	Mean dias. range from	to
* Superstructures	Good	Rule length	275 fms Dia. 2" SQ
* Skylights	Good	Mooring ropes	Sufficient
* Companionways	Good		
* Hatchways	Good		
* Ventilators	Good		
Other items:	None		

* These items to include their closing appliances

Where a part Special Survey and, say, Dry Docking Survey are held at the same time, the items for SS should be marked "For SS"



© 2021

Shoguchi
Surveyor to Lloyd's Register of Shipping

S. Noguchi

HOLDS & 'TWEEN DECKS:		Examined & condition	TANKS:	Examined & condition	Tested & condition
No. 1	Hold	Good	F.P. tank	Good	Good
„	'Tween decks	Good	A.P. tank	Good	Good
			D.B. tanks & c/dams		
			All O.F. D.B.T.	-	Good
			All F.W., W.B.	Good	Good
			D.B.T. & C/dams		
No. 2	Hold	Good			
„	'Tween decks	Good			
No. 3	Hold	Good	O.F. bunkers	-	-
„	'Tween decks	Good			
			Settling tanks	-	-
No. 4	Hold	Good			
„	'Tween decks	Good			
			Deep tanks	Good	Good
No. 5	Hold	Good			
„	'Tween decks	Good	Side tanks	-	-
No. 6	Hold	-	Wing tanks		
„	'Tween decks	-	Tunnel Wing	Good	Good
			P.&S.		
			Other tanks:	-	-
	Cargo battens	Good			
	Ceiling, etc.	Good			



© 2021

Lloyd's Register
Foundation

Rpt. 8 (Rig)

Ship's Name SS/MS NAGAOSAN MARU

(Matter above line is completed by Lloyd's Register of Shipping) Port Kobe Rpt. No.

Port of KOBE

Date 15th-Aug., 1964.

REPORT ON MASTS, SPARS AND RIGGING

Dear Sir(s),

In accordance with your instructions, I examined the Masts, Spars and Standing Rigging, including fittings, of the SS/MS NAGAOSAN MARU

on the (date of examination) 15th-Aug., 1964.

and found that Good condition

[Empty dotted lines for additional text]

Fee Rigger

To the Surveyor(s), Lloyd's Register of Shipping,

M. Kashiwada MITSUI SHIPBUILDING & ENGINEERING CO., LTD. CHIEF OF REPAIRING SECTION. Surveyor Shojiuchi



© 2021

Lloyd's Register Foundation

0208 33