

COPY

Lloyd's Register of Shipping.

No. M-52181

Port KOBE

25th September, 1958.

This is to Certify that

Y. KOJIMA,

undersigned Surveyor to this Society did at the request of Messrs. Ishii Kosakusho Co., Ltd., Osaka attend at their works on the 27th September, 1958 and subsequently for the purpose of inspecting and testing

One (1) 75HP Steam reciprocating compound engine (Machine No.2062) for 4 M3 air compressor

intended for Ship No.635 being built by Mitsui Shipbuilding & Eng., Co., Ltd., Tamano Works, Tamano.

Particulars:-

H.P. cylinder bore	265mm
L.P. " "	394mm
Length of Stroke	150mm
No. of revolutions	500 r.p.m.
Working pressure	12 kg/cm ²
Exhaust pressure	0.5 "

This steam reciprocating compound engine was tried under working conditions in accordance with the Shipbuilders Specification with satisfactory result.

The steam cylinder, governor cylinder, steam separator and drain receiver were subjected to hydraulic pressure - 20, 20, 20 and 4 kgs/cm² and found sound and tight.

Identification marks:-

LLOYD'S TEST KOB	
W.T.P. 20,20,20 or 4 kg	
KK	27-6-58
MH	4-7-58 LR
HI	25-7-58

SHOP TRIAL	
YK	LR
17-9-58	

Surveyor to Lloyd's Register.

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that: "While the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly conducted, it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."

YK:tk 014887-014898-0083