

26 SEP 1941

Received by Chief Ship Surveyor.....

Received from Chief Ship Surveyor.....

VESSEL'S NAME..... ELNA II Rpt. Nwc No. 99754

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/92.)

The class is subject to set in 4th plate from aft in 3rd strake below sheerstrake (s.s) and 3rd plate from aft in 3rd strake below sheerstrake (p.s) and framing in way being permanently repaired at the first convenient opportunity.

Action has been deferred for repairs to shell, double bottom, tank top etc. in No. 3 hold (enemy action).

The NEWCASTLE Surveyors report the vessel placed in dry dock, bottom coated, and the damage from enemy action as above now dealt with by renewals or repairs to shell plates, frames, inner bottom, decks, rudder, tank top, steering arrangements, hatchways, bulkheads etc.

Stiffening for armament has been fitted in the poop, and additional accommodation within the bridge space. Temporary wood deck for passenger accommodation has been laid throughout the holds, on existing hold stringers and beams, and on additional beams with suitable pillars, girders and tie plates in way of hatchways (all bolted.)

After completion the new decking was lifted and stowed on board and the lower holds filled with ballast and cargo.

No. 2 D.B. tank now adapted for carrying fresh water, and the plugs in holes on centre keelson removed.

The indented plating as above examined and found efficient.

It is submitted the vessel appears worthy to remain as classed with record of survey 8.41, subject as above.

Delete from S.R.L.: - Rps (enemy action)



© 2021 23.9.41

Lloyd's Register
Foundation

014935-014945-0221