

ADMIRALTY TRAWLERS.

"CASTLE" Class.

6 Steel Screw Steamers (Nos. ²⁰¹⁻²⁰⁶ ~~not given~~) to be built by Messrs. C. Rennoldson & Co., with a view to class 100A1 "Steam Trawler".

Rule Dimensions:- 125 x 23.37 x 13.5

Scantling Nos.:- 36.87 and 4608.

Proportions:- Length = 9.26 Depths.

Plans of Midship Section, Profile & Decks submitted by Mr. Macdonald.

These vessels are duplicates of the other "CASTLE" Trawlers already building for the Admiralty.


It is submitted that provided

COMPLIANCE

the vessels will be eligible to be classed 100A1 "Steam Trawler".

The Surveyors should point out to the Builders that in view of the beams being fitted on every frame they may be reduced to .30 in thickness and the deck plating reduced to .28 in thickness fore and aft, ^{excepting under winch & windlass} as indicated on the plans.

The duplicate copies have been retained in this Office for reference.



25.1.18.

22-1-18
And: 25.
Plans retained



© 2021

Lloyd's Register
Foundation

014946-014960-0186