





[illegible]

EQUIPMENT No.				LETTER				ANCHORS.				TONNAGE U.D.K. OR PLATING No. FOR TRAWLERS				4600.									
Number of Certificate.		Anchors.		WEIGHT, EX STOCK		WEIGHT OF STOCK		TEST, PER CERTIFICATE.		WEIGHT REQUIRED BY TABLE 31.		Description of Anchor		Makers.		Where and when tested and Superintendent.									
		Cwts.	qrs.	lbs.	Cwts.	qrs.	lbs.	Tons.	cwts.	qrs.	lbs.	Cwts.	qrs.	lbs.											
30470 51387	1st Bower ... 2nd " ... 3rd " ... 4th " ... Collective weight. Stream .....	8	2	2	✓			10	12	2	0	7	2	1	Stockless	H. Griffin & Co. Ltd., 1 Wright St.	Callahan, 31/12/18 Rod Tipton 25/10/18 Lead								
81828	Kedge.....	3	0	8	✓	0	3	3	5	12	0	21	-	Common	Wingley	Milner 6/11/19 Green									
Particulars of Drop Test of Cast Steel Anchors, viz.:— Weight, Surveyor's Initials, Number of Certificate, Date of Test.				1st Bower head wt 5-1-14 25-9-17 D.D.N. Sld. 1175 - forged head. 2nd " 3rd " 4th "																					
CHAIN CABLES.																HAWSERS AND WARPS.									
Number of Certificate.		Length and size supplied.		Test per Certificate.		WEIGHT OF CHAIN CABLE.		Length and Size per Table 31.		Description.		Makers of Cables.		Where and when tested, and Superintendent.		Material.		Length and size supplied.		Breaking Test of Steel Wire Towline.		Length and Size per Table 31.			
		Fathoms.	Inches.	Tons.	Tons.	Cwts.	qrs.	lbs.	Cwts.	qrs.	lbs.	Fathoms.	Inches.					Fathoms.	Inches.	Tons.	Fathoms.	Inches.			
52103	105 3/4	1 1/2	✓	30 3/4	63	2	14	60	2	15	105	1 1/2	Steel	Lanarkshire Works	21/10/18. Tipton, Bureau	✓	TOWLINE	60	2 3/4	13 1/2	60	2 3/4	13 1/2	60	2 3/4
		Cir.																							
Boats		one 16'6" x 6'8" x 2'5"														Steering Gear, Steam		Steering Gear, Hand P. Regen Co							
Pumps, Number		4 hand pumps														Diameter of Barrel 4"		State whether they are in efficient working order Yes							
Windlass is		Emerson Walker, Hand — may be worked by muscled from front which steel														Capstan									
Engine Room Skylights.—How constructed?		What arrangements for deadlights in bad weather? screw down																							
Coal Bunker Openings.—How constructed?		Cast Iron Scabbles														How are lids secured? locked		Height above deck? flush.							
Number of Scuppers, and numbers and dimensions of Freecing Ports, &c.		6 scuppers each side, 4 ports each side 18" x 14"																							
Ceiling in Holds, thickness and material		Fish hold lining														Cargo Battens, thickness and material									
Cargo Hatchways.—How formed?		X														Hatches, If strong and efficient? X									
State size No. 1 Hatch (Forward)		No. 2 Hatch														No. 3 Hatch		No. 4 Hatch							
Number of Web Plates, Shifting Beams and Fore and Afters to each Hatch		X														No. of Breasthooks deep floors		No. of Crutches deep floors and peak flat							
																Main Rail, material and size 7"x3"x7/20 Bull duple									
Bulwarks, height above deck and description		2'-11" steel																							
The foregoing is a correct description.		Surveyor's Signature J. Macdonald														Builder's Signature (here only) James Kennedy & Co.		Surveyor to Lloyd's Register of Shipping.							
Correspondence.—State dates and initials of letters respecting this case (Reference should be made in any correspondence connected with the case) see correspondence for Castle Type Trawlers.																									
Workmanship. Are the butts of plating planed or otherwise fitted? planed - Clefped																									
Is the riveted work properly closed? Yes																									
Are the liners between the frames and plates solid single pieces? Joggled frames																									
Do the holes for riveting plate to frames, butt straps, or plate to plate, &c., conform well to each other? Yes																									
Are the rivet holes well and sufficiently countersunk in the plate and punched from the facing surfaces? Yes																									
Do any rivets break into or through the seams or butts of the plating? very few.																									
Are the butts of Plating, Stringers, &c., properly shifted and strapped? Yes																									
Have all the upper and weather decks been tested as required by the Rules (Sec. 26, par. 20)? Yes State results of tests satisfactory																									
Have all the gutterways been tested as required by the Rules (Sec. 26, par. 20)? Yes State results of tests satisfactory																									
General Remarks (State quality of workmanship, &c.)																									
This vessel has been built in accordance with approved Midship Section Admiralty Specification + Plans as modified from time to time by Admiralty for Castle Type Trawlers.																									
None of the armament or war appliances fittings have been fitted and vessel has been completed as a Fishing Vessel. She has been sold by Admiralty to the EBOR FISHING Co..																									
The workmanship and materials are good and to our satisfaction.																									
Approved plans of Midship Section and print of Midship section as built are forwarded herewith																									
Nos 202-3-4-5-6 By same builders are sisters to this vessel.																									
The Surveyor should state the Number of Report and Name of any Sister Vessel. Plans to be forwarded with F.E. Report showing vessel as built.																									
Fees applied for, 22/9/1919 Received by me, 11/10/1919 RPBW																									
Certificate to be sent to Newcastle Date of issue 13.10.19.																									
The amount of Entry Fee £ 30 : 6 : Travelling Expenses, if any £																									
State whether the Vessel has been built under Special Survey yes																									
I am of opinion this Vessel should be Classed +100A1 "FOR FISHING PURPOSES" without																									
With, or without Freeboard, as condition of Class.																									
Committee's Minute																									
Character assigned 100A1 Steam trawler																									
Lloyd's a/c P. LMC 8.19 Mh																									

© 2021 Lloyd's Register Foundation



GENERAL REMARKS—(continued).

PARTICULARS FOR RECORD in the REGISTER BOOK.—Length of Poop — ft., R.Q.D. 72.2 ft., Bridge — ft., Forecastle 22 ft.  
(in feet and tenths). When the Poop is joined to the B.D., this should be distinctly stated

No. and Material of Decks (if Iron or Steel) and whether wholly or partially covered with wood, and No. of tiers of Beams (this information is to be given as it should appear in the Register Book) 1 dk pt slt

Official No. 136086 ; Signal Letters State if Machinery is fitted aft MCHY AFT  
How are the surfaces preserved from oxidation? Inside Cement Paint Outside paint

PARTICULARS OF WATER BALLAST.—State whether the Double bottom is constructed on the cellular system or with girders on floors

Where Fitted.	Length. Feet.	Water Capacity. Tons.	Where Fitted.	Length. Feet.	Water Capacity. Tons.
Double bottom, aft,	—	—	Fore peak tank,	—	—
Double bottom, under Engines and Boilers,	—	—	After peak tank,	—	2.75
Double bottom, if under Engines only,	—	—	Deep tank, aft,	—	—
Double bottom, if under Boilers only,	—	—	Deep tank, forward,	—	—
Double bottom, forward,	—	—	Other tanks, if fitted,	—	—
Total capacity of double bottom	—	—	(If necessary, furnish further information by sketch.)	—	—

\* The wells are not to be included in the lengths of the tanks.

State whether the above have been tested as required by the Rules. yes

Order for Special Survey No. 4778.

Date 24-8-18.

No. 201 in builder's yard.

DATES of Surveys held while building

July 17, 22 Aug 1, 14 21, 30. Sept 3, 10, 12, 17, 24, 28. Oct 7, 16, 25 Nov 1, 7, 14, 21 Dec 2, 9, 16, 23, 30. Jan 5, 12, 19, 26. Feb 2, 9, 16, 23. Mar 5, 12, 19, 26. Apr 5, 12, 19, 26. May 5, 12, 19, 26. Jun 5, 12, 19, 26. Jul 5, 12, 19, 26. Aug 5, 12, 19, 26. Sep 5, 12, 19, 26. Oct 5, 12, 19, 26. Nov 5, 12, 19, 26. Dec 5, 12, 19, 26.

Total No. of Visits 41

Surveyor's Signature

J. Macdonald

© 2021

Lloyd's Register Foundation