

Port of London19-11-1947**REPORT ON MASTS, SPARS, AND RIGGING.**

Having, in accordance with your instructions,
 examined the Masts, Spars, Iron Work of same, and Rigging, of the
 name of Vessel M.V. (EX AN 76)

the (Date of examination) November 19TH 1947,

we to report that I found

JOB NO. 397.

M.V. "PRETEXT"

10th November, 1947.

Rigging Survey.

Foremast (Wood) Good condition.

Spiderbands and lugs in good condition.

Yardlifts to clean and oil, Rigging screws and shackles to overhaul.

Shrouds 4" S.F.W. 3 pr. side to clean and oil, reserve where required. Screws, slips and shackles to overhaul.

No forestays on mast.

All shrouds set up with stehouse slips and open screws.

Mainmast (Wood) Good condition.

Spiderbands and lugs in good condition.

Yardlifts to clean and oil, splices to re-serv and screws and shackles to overhaul.

Shrouds and twinstays 2" S.F.W. to clean and oil, splices to reserve where required.

Rigging screws and shackles to overhaul.

All shrouds and stays fitted with insulators, 2 Pr. stay.

£ / : : _____

The Surveyors,

Lloyd's Register of Shipping,

E. Leatham



© 2021

Lloyd's Register
Foundation