

COPY

118 MAY 1953

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER



Port TRINIDAD, B.W.I.

30th. April, 1953.

This is to Certify that

J. B. STARK

the undersigned Surveyor to this Society did at the request of Messrs. Trinidad Shipping Co.Ltd., Owners of the s.s." TRANSFORD II" of Port of Spain, Trinidad, 1736 tons gross, on the 1st. April, 1953 and subsequent date, attend at Messrs. Furness Withy Ltd., Port of Spain, Trinidad, on account of repairs to two spare Screw Shafts for the above vessel.

The shafts, which are fitted with continuous liners, were badly worn in way of same, particularly at the after ends.

Forty and one half inches was cut from the after ends of the liners, and new lengths of similar material shrunk on and Si6ronze welded at the butt of the remaining portion of liner in each case. The finished diameter was 9 1/8" and the inboard end of the old liner was skimmed down to a diameter of 9" full.

I certify herewith that the shafts are suitable for a further term of service.

Surveyor to Lloyd's Register of Shipping.

015302-015315-0380

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that :—

While the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly performed, it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances ever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."

