

MAIN PIECE OF RUDDER TO BE TURNED DOWN 4'-0" FROM HEAD 9" DIA.
HOLES FOR PINTLES TO BE CENTRED 42" FROM FORESIDE OF RUDDER FRAME.
HEAD & HOLES FOR HEEL & PINTLES TO BE TURNED IN A LATHE SO AS TO GET THEM
QUITE TRULY CENTRED. CHECK THE HEIGHTS OF GUDGEONS ON RUDDER FRAME
FROM THE HEIGHTS OF GUDGEONS ON SCREW FRAME & MAKE THEM CORRESPOND.

Rudder Han
W. Gray. 16th
ss. N. 785.

ss. "Hans B"
Spec. Report No. 14140



© 2021

Lloyd's Register
Foundation

015316-015324-0126