

Fld. 1916

31149

Index No.

## Lloyd's Register of Shipping

29 JAN 1943

Ship's Name "TLOUCA"

SIGNAL LETTERS:-

Official No. LDAY

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines

The following alterations now effected:-

A steel companionway of substantial construction now fitted on port side of shelter deck tonnage hatch, on steel foundation plate E.W. to hatch coaming; sill 18" high; opening closed by strong wood door fitted with spring lock.

Stormboard openings in forward bulkhead in tonnage well now closed by riveted steel plates.

Three sidelights, with strong hinged deadlights, fitted to shell plating in tonnage well, p. & s. Overboard sanitary discharges from new gunners' accommodation in tonnage well fitted with non-return screwdown valves controlled from shelter deck.

Freeing port doors and drain scuppers in well closed by E.W. and two 5" diameter screwdown non-return valve overboard scuppers fitted, controlled from shelter deck.

Three ventilators fitted on shelter deck in way of new accommodation in tonnage well, one port and one at centre each 9" diameter with coamings 3 ft. high, wood plugs and canvas covers; one starboard side 6" diameter with coaming 3 ft. high, wood plugs and canvas covers.

All overboard scuppers in shelter deck closed by E.W. plates; and two 3" diameter pipe scuppers fitted p. & s. amidships, draining to the machinery space bilges.

H. W. Edwards

H. W. Edwards

29 JAN 1943

Hull 26/1/43



© 2021

Lloyd's Register  
Foundation

015338-015347-0175