

Rpt. 13.

No. 29666

REPORT ON ELECTRIC FITTINGS.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

Received at London Office

Date of writing Report

19

When handed in at Local Office

10 MAR 1928

Port of

Newcastle-on-Tyne

SUNDERLAND.

No. in Survey held at

Sunderland

Date, First Survey

Jan 10

Last Survey

Mar 8 1928

Reg. Book. Suff.

(Number of Visits.....7.....)

42778 on the

St. Therese.

Tons { Gross 2280

Net 1354

Built at Sunderland.

By whom built Swan Hunter & Wigham Richardson

Card No. 1327

When built 1928

Owners J. Lund & Co.

Port belonging to Jonsberg.

Electric Light Installation fitted by Messrs Campbell & Sheerwood & Co.

Contract No. 1327. When fitted 1928.

System of Distribution

Double wire

Pressure of supply for Lighting

110

volts, Heating

volts, Power

volts.

Direct or Alternating Current, Lighting

Direct

Power

If alternating current system, state frequency of periods per second

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off. Yes

Generators, do they comply with the requirements regarding rating. Yes, are they compound wound. Yes.

are they over compounded 5 per cent. Yes, if not compound wound state distance between each generator.

Where more than one generator is fitted are they arranged to run in parallel. Yes, is an adjustable regulating resistance fitted in series with each shunt field.

Are all terminals accessible, clearly marked, and furnished with sockets. Yes, are they so spaced or shielded that they cannot be accidentally earthed, short circuited, or touched. Yes. Are the lubricating arrangements of the generators as per Rule. Yes.

Position of Generators Engine room starboard side

is the ventilation in way of the generators satisfactory. Yes, are they clear of all inflammable material. Yes

if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators. Yes, are the generators protected from mechanical injury and damage from water, steam or oil. Yes

are their axes of rotation fore and aft. Yes

Earthing, are the boltpats and frames of the generating plant efficiently earthed. Yes, are the prime movers and their respective generators in metallic contact. Yes.

Main Switch Boards, where placed Engine room starboard on after bulkhead.

If the generators and main switchboard are not placed in the same compartment, is each generator provided with a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard. Yes

Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes. Yes, are they protected from mechanical injury and damage from water, steam or oil. Yes, if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards. Yes

are they constructed wholly of durable, non-ignitable non-absorbent materials. Yes, is all insulation of high dielectric strength and of permanently high insulation resistance. Yes, if semi-insulating material is used, are all conducting parts insulated from the slab with mica or micaite or other non-hygroscopic insulating material, and the slab similarly insulated from its framework. Yes

and is the frame effectively earthed. Yes. Are the fittings as per Rule regarding: - spacing or shielding of live parts. Yes, accessibility of all parts. Yes, absence of fuses on back of board. Yes, proportion of omnibus bars. Yes, individual fuses to voltmeter, pilot or earth lamp. Yes, connections of switches. Yes


Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches. Double pole switch & fuses on dynamo mains. Single pole switch & double pole fuses on each outgoing circuit

Instruments on main switchboard one ammeters one voltmeters synchronising device for paralleling purposes.

Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system. Earth lamps coupled to earth through switches & fuses.

Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules. Yes

Joint Boxes Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule. Yes



© 2021

Lloyd's Register Foundation

015366 - 015379 - 0410

Cables: Single, twin, concentric, or multicore single twin are the cables insulated and protected as per Tables IV or V of the Rules. Yes

Fall of Pressure, state maximum between bus bars and any point of the installation under maximum load 4.0 volts

Cable Sockets and other connections, are the ends of all cables having a sectional area of 0.04 square inch and above provided with soldering sockets Yes

Paper Insulated Cables, If cables are paper covered, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound Yes

Cable Runs, are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage Yes.

Support and Protection of Cables, state how the cables are supported and protected Lead covered & tinned cables in machinery spaces. V.I.R. in steel pipe in tween decks & cargo spaces. Lead covered cables in cabins
If cables are run in wood casings, are the casings and caps secured by screws Yes, are the cap screws of brass Yes, are the cables run in separate grooves Yes. If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VIII Yes

Refrigerated Chambers, if lights are fitted, are the cables and fittings in accordance with the special requirements Yes

Joints in Cables, state if any, and how made, insulated, and protected none made

Watertight Glands and Deck Tubes, are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands Yes

Bushes in Beams and Non-watertight Partitions, where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed Yes state the material of which the bushes are made Lead

Earthing Connections, state what earthing connections are fitted and their respective sectional areas Yes
are their connections made as per Rule Yes

Alternative Lighting, are the groups of lights in the propelling machinery spaces arranged as per Rule Yes

Emergency Supply, state position and method of control of the emergency supply and how the generator is driven none fitted

Navigation Lamps, are these separately wired Yes, controlled by separate switch and separate fuses Yes, are the fuses double pole Yes
are the switches and fuses grouped in a position accessible only to the officers on watch Yes
has each navigation lamp an automatic indicator as per Rule Yes

Secondary Batteries, are they constructed and fitted as per Rule Yes

Fittings, are all fittings on weather decks, in stokeholds and engine rooms and where exposed to drip or condensed moisture, watertight Yes
are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected Yes
are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected Yes
how are the cables led Yes
where are the controlling switches situated Yes

Searchlight Lamps, No. of Yes, whether fixed or portable Yes, are their fittings as per Rule Yes

Are Lamps, other than searchlight lamps, No. of Yes, are their live parts insulated from the frame or case Yes, are their fittings as per Rule Yes

Motors, are their working parts readily accessible Yes, are the coils self-contained and readily removable for replacement Yes
are the brushes, brush holders, terminals and lubricating arrangements as per Rule Yes, are the motors laced in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material Yes
are they protected from mechanical injury and damage from water, steam or oil Yes are their axes of rotation fore and aft Yes
if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated forced draught, drip or flame proof type Yes, if not of this type, state distance of the combustible material horizontally or vertically above the motors Yes and Yes

Control Gear and Resistances, are the generator field and motor speed regulators, starters and controllers constructed and fitted as per Rule Yes

Lightning Conductors, where lightning conductors are required, are these fitted as per Rule Yes

Ships carrying Oil having a Flash Point less than 150° F. Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings Yes
If portable lamps for use in dangerous spaces are supplied, are they of a type approved by the Home Office Yes

PARTICULARS OF GENERATING PLANT.

DESCRIPTION OF GENERATOR.	No of	RATED AT			Revs. per Min.	DRIVEN BY.	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE.	
		Kilowatts.	Volts.	Ampères.			Fuel Used.	Flash Point of Fuel.
MAIN	1	7.5	110	68.0	400	Single cylinder steam engine		
AUXILIARY								
EMERGENCY								
ROTARY TRANSFORMER								

LIGHTING AND HEATING CONDUCTORS.

Ref. No.	DESCRIPTION.	No. of Conductors.	Effective Area of each Conductor. Sq. Ins.	COMPOSITION OF STRAND.		Total Maximum Current. Amperes.	Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
	MAIN GENERATOR	2	.06	19	.064	68	26	V.I.R.	Lead covered
	EQUALISER CONNECTIONS								
	AUXILIARY GENERATOR								
	EMERGENCY GENERATOR								
	ROTARY TRANSFORMER								
	AUXILIARY SWITCHBOARDS								
	ENGINE ROOM								
	BOILER ROOM	2	.00485	7	.029	7.0	6	50	Lead covered
	ACCOMMODATION midships	2	.02214	7	.064	34.0	65	50	50
	50 aft	2	.00485	7	.029	8	150	50	In steel pipe
	Navigation	2	.00485	7	.029	6	150	50	50
	WIRELESS	2	.00701	7	.036	12	160	50	50
	SEARCHLIGHT								
	MASTHEAD LIGHT	2	.00194	3	.029	.5	200	50	Lead covered
	SIDE LIGHTS	2	.00194	3	.029	.5	46	50	50
	COMPASS LIGHTS	2	.00194	3	.029	.25	20	50	50
	STERN LIGHTS	2	.00194	3	.029	.5	260	50	50
	CARGO LIGHTS	2	.0017	16	.012	3.0	60	50	Lead protected
	ARC LAMPS								
	HEATERS								

MOTOR CONDUCTORS.

Ref. No.	DESCRIPTION.	No. of Motors.	Effective Area of each Conductor. Sq. Ins.	COMPOSITION OF STRAND.		Total Maximum Current. Amperes.	Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
	BALLAST PUMP								
	MAIN BILGE LINE PUMPS								
	GENERAL SERVICE PUMP								
	EMERGENCY BILGE PUMP								
	SANITARY PUMP								
	CIRC. SEA WATER PUMPS								
	CIRC. FRESH WATER PUMPS								
	AIR COMPRESSOR								
	FRESH WATER PUMP								
	ENGINE TURNING GEAR								
	ENGINE REVERSING GEAR								
	LUBRICATING OIL PUMPS								
	OIL FUEL TRANSFER PUMP								
	WINDLASS								
	WINCHES, FORWARD								
	WINCHES, AFT								
	STEERING GEAR								
	(a) MOTOR GENERATOR								
	(b) MAIN MOTOR								
	WORKSHOP MOTOR								
	VENTILATING FANS								

All Conductors are of annealed copper conforming to British Standard Specification No. 7.
 The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.
 The foregoing is a correct description.

CAMPBELL & SPERWOOD, LTD.

Thomas Meade

Electrical Engineers.

Date *22/ March 1928*

COMPASSES.

Distance between electric generators or motors and standard compass *109 feet*
 Distance between electric generators or motors and steering compass *100 feet.*
 The nearest cables to the compasses are as follows:—
 A cable carrying *.25* Amperes *on the* ~~feet from~~ standard compass *10* feet from steering compass.
 A cable carrying *.25* Amperes *10* feet from standard compass *on the* ~~feet from~~ steering compass.
 A cable carrying _____ Amperes _____ feet from standard compass _____ feet from steering compass.
 Have the compasses been adjusted with and without the electric installation at work at full power *Yes*
 Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted *yes*
 The maximum deviation due to electric currents was found to be *nil* degrees on *all* course in the case of the standard compass, and *nil* degrees on *all* course in the case of the steering compass.

FOR

SWAN HUNTER & WIGHAM RICHARDSON LTD,

Thomas Meade Builder's Signature.

Date *8 Feb. '28*

Is this installation a duplicate of a previous case *no* If so, state name of vessel _____

General Remarks (State quality of workmanship, opinions as to class, &c.)

The above installation is in accordance with the Society's Rules. The vessel is eligible in my opinion for notation elec light wireless

It is submitted that
 this vessel is eligible for
 THE RECORD

Elec Light

W.T. Badger
 16/3/28

Total Capacity of Generators *7.5* Kilowatts.

The amount of Fee ... £ *8* : : *1 March 1928*

Travelling Expenses (if any) £ : : *23.3.28*

W.T. Badger

Surveyor to Lloyd's Register of Shipping.

Committee's Minute _____

Assigned _____

Elec light

Im. 1.28.—Transfer.
 (The Surveyors are requested not to write on or beside the space for Committee's Minute.)



© 2021

Lloyd's Register
 Foundation