

Preliminary Report Form No 9 attached Index No. 32434
Lloyd's Register of Shipping No. 29484
SURVEYS FOR FREEBOARD.—STEAM SHIPS.

PARTICULARS RELATING TO ALL STEAM SHIPS EITHER FLUSH DECKED, OR WITH TOP GALLANT FORECASTLES, SHORT POOPS AND BRIDGE HOUSES DISCONNECTED, OR WITH TOP GALLANT FORECASTLES HAVING LONG POOPS, OR RAISED QUARTER DECKS CONNECTED WITH BRIDGE HOUSES, OR OTHERWISE.

Port of Survey Sunderland
Date of Survey 29th July 1927
Name of Surveyor L. H. Dixon

Ship's Name <u>Swan Hunter & Digham Richardson</u> No 1327	Port of Registry and Nationality <u>✓</u>	Official Number <u>✓</u>	Gross Tonnage <u>✓</u>	Date of Build <u>1927</u>	Particulars of Classification <u>* 100 A1 Contemplated</u>
Number in Register Book <u>✓</u>	<u>✓</u>	<u>✓</u>	<u>✓</u>		

Registered mensions from Ship's Register <u>Given</u>	LENGTH. <u>293.08</u>	BREADTH. <u>44.16</u>	DEPTH. <u>19.34</u>	UNDER DECK TONNAGE. <u>2010</u>
Length on LOADLINE.	<u>292.00</u>	Frame Depth Rule <u>5 1/2</u> <u>3+2 = .50</u> <u>for Ceiling fitted</u>	Ceiling <u>fitted</u> Sheer <u>+ .66</u>	Peak Tanks <u>included</u>
CORRECTED DIMENSIONS.	<u>292.0</u>	<u>43.66</u>	<u>20.00</u>	<u>2010</u>

Moulded Depth as ~~measured~~ Given 21-6
 Addition for Keel below base line - for draught record... 1.98...inches.
 NOTE.— If the depth is measured when vessel is afloat, the details of measurement should be reported.

Co-efficient of fineness..... .79 .788
 Any modification necessary } .02 CDB
 [Para. 4 (a) to (e)]* }
 Co-efficient as corrected77

CORRECTION FOR LENGTH

Length of Ship on Loadline.....	<u>292</u>
Length in Table	<u>258</u>
Difference	<u>34</u>
Correction for 10ft., Table A.	<u>1.2</u>
× Difference divided by 10	<u>40.8</u>
If 1/10ths length covered divide by 2	<u>+ 4</u>

Sheer { Stem..... 84 } 126 ÷ 2 = 63 ...Mean .66
 at { Sternpost ... 42 }
 Sheer at 1/3 of the length from { Stem 46.25 } 69.50 ÷ 2 = 34.75...Mean .55 = 63.18
 { Sternpost 23.25 }
 Gradual mean Sheer allowed 63.09
 Standard mean Sheer [Table, Para. 18] 39.20 Correction .097
 Difference..... 23.89 ÷ 4 = 5.95
 § If limited as Para. 18 (f) - 6"

CORRECTION FOR IRON DECK.
 Proportion covered, if less than 1/10ths length covered ... 4332
 Thickness of usual wood deck, less stringer 3 1/2"
1.52 - 1 1/2"

Rise in Sheer { At front of bridge house..... }
 from amidships { [Para. 18 (e)] } At after end of forecastle

Fall in Sheer }
 Para. 18 (d) } ÷ 2 =
 Length uncovered Correction

CORRECTION FOR ROUND OF BEAM.
 Breadth at Gunwale amidships..... 43.8
 Round of Beam 10 1/2
 Normal round..... 10 7/8 91
 Difference 3/8 41 ÷ 2 = 7/16 .20
 Proportion of Deck uncovered (Para. 19)56
.11

ALLOWANCE FOR DECK ERECTIONS :—

Freeboard, Table C.....	<u>1-8 1/4</u>
Correction for Length, if required (Para. 12, 13, and 14)	<u>+ 2</u>
Freeboard by Table A, corrected for sheer, and for length, if required (Para. 12, 13, and 14) }	<u>4-2</u>
Difference	<u>2-3 3/4</u>
Percentage as below.....	<u>27.324%</u>
	<u>= 7-58</u>

Freeboard, Table A	<u>4 4</u>
Correction for Sheer	<u>- 6</u>
Correction for Length	<u>+ 4</u>
Allowance for Deck Erections	<u>- 7 1/2</u>
Correction for Round of Beam.....	<u>3-6 1/2</u>
Correction for fall in Sheer (if any).....	<u>-</u>
Correction for Steel Deck (if required)	<u>- 1 1/2</u>
Additions for non-compliance with provisions of Para. 11 (d) and (e) †	<u>3-5</u>
Other Corrections (if any)	<u>3-2 1/2</u>

Correction for R. Q. Dk. if engine and boiler openings not covered by bridge house (Para. 11) - 7 1/2
 Allowance for Deck Erections - 7 1/2

Winter Freeboard 3-5
 Summer Freeboard 3-2 1/2
 Indian Summer Freeboard 3-0 2-11
 N. A. Winter Freeboard 3-7

	Length.	Length allowed.	Height.
Forecastle.....	<u>25-4 1/2</u>	<u>25.38</u>	<u>7-6</u>
Bridge House	<u>76-0 including workways</u>	<u>74.50</u>	<u>7-6</u>
† Raised Qr. Dk.....			
Poop.....	<u>26-7 1/2</u>	<u>26.62</u>	<u>7-6</u>
Total	<u>128-0</u>	<u>126.50</u>	<u>.4332</u>
Length of Ship	<u>292</u>	<u>292</u>	
Corresponding percentage (Para. 11, 12, 13, or 14) }	<u>27.324%</u>		

Correction necessary because clearside amidships, measured in accordance with the Statute is not taken at the intersection of the wood or steel deck with side. 1 1/2
 $10.5 - 10.5 \left(\frac{20.25}{22} \right)^2 = 1.61$

Winter Freeboard from deck line	<u>3-6 1/2</u>
Summer " " " "	<u>3-4 3/2</u>
Indian Summer " " " "	<u>3-7 1/2 0 1/2</u>
N. A. Winter " " " "	<u>3-8 1/2</u>

FREEBOARD recommended amidships from centre of Disc to top of Statutory Deck Line, Wood (Steel) Deck :—

Fresh Water Line above centre of Disc	<u>4 1/2</u>
Indian Summer Line " " " "	<u>3</u>
Winter Line below " " " "	<u>3</u>
Winter North Atlantic Line " " " "	<u>5</u>

Winter Freeboard from deck line 3-4 3/2
 Summer " " " " 4 1/2
 Indian Summer " " " " 2 1/2 3
 N. A. Winter " " " " 2 1/2 3
 4 1/2 5

† If the frames, skin planking, or ceiling are of unusual thickness the breadth of vessel to inside of ceiling should be reported if possible.
 † In vessels obtaining an allowance for deck erections under Para. 11 where the sheer drops abaft amidships the height of the R.Q.D. is to be taken from the level of the top of the amidship beam.
 § In flush-decked vessels the total standard mean sheer means the sheer measured at the stem and sternpost. In vessels having poops and forecastles, it means the sheer measured at points distant one-eighth of the vessel's length from stem and sternpost.

† State dimensions of freeing port area on back of this form.
 † The Surveyor should state whether the fall in sheer as reported is measured relatively to the straight line of keel or to the water line. If measured relatively to water line the vessel's draft at time of survey, and also the usual load draft forward and aft should be reported.

Do all the Frames extend to the top height in the Poop? *Yes* Raised Quarter Deck? *✓* Bridge House? *Yes* Forecastle? *Yes*
 To what height do the Reverse Frames extend? *Butt angle frames*
 Has the Poop or Raised Quarter Deck an efficient Iron Bulkhead at the fore end? *Yes - Steel*
 Give particulars of the means for closing the openings in Bulkhead *no openings*
 Is the Poop or Raised Quarter Deck connected with the Bridge House? *no* Has the Bridge House an efficient Bulkhead at the fore end? *Yes*
 Give particulars of the means for closing the openings in Bulkhead *no openings*
 What is the thickness of the Bridge Front plating? _____ and Coaming plate? _____
 Give scantlings and spacing of the Stiffeners _____ } *rule*
 Are bracket plates fitted at each end of the Stiffeners? _____ Are hor'l. brackets fitted connecting Bridge Bulk'd. with Bulwarks? _____
 Has the Bridge House an efficient Iron Bulkhead at the after end? *Yes*
 How are the openings closed? *hinged channels + storm boards full height*
 Is the Forecastle at least as high as the main or top-gallant rail? *Yes* Has the Forecastle an efficient Iron or Wood Bulk'd. at after end? _____
 Are the Engine and Boiler openings covered by a Bridge, Poop, Raised Quarter Deck, or enclosed by a Strong Iron or Steel Deckhouse?
 If the openings are not so protected are the exposed parts of the Casings efficiently constructed? *rule*
 Give thickness of plating; scantlings and spacing of Stiffeners _____
 What is the height of the exposed Casings? _____ Are suitable means provided for closing all openings in them in bad weather? _____
 Are the Weather Deck Hatchways efficiently constructed and at least equal to the requirements of Section 28 of the Rules for 1904-5? Give particulars below:—

Position and Size.		Ship.	Rule.								
Item.											
COAMING.	Height above top of DECK										
	Thickness { Sides..... Ends.....										
SHIFTING BEAMS OR WEE PLATES.	Number										
	Section and Scantlings										
	Material										
* FORE AND AFTERS.	Number										
	Section and Scantlings										
	Material										
HATCHES	Thickness										
	Remarks.....										

all to rule


* The depth of Fore and Afters should be stated from the underside of the hatches in all cases.
 (If the sill of the lowest side scuttle will be less than 6 inches above the Indian Summer Load Line if assigned under the tables, state vertical distance from top of deck at side amidships to lower edge of lowest side scuttle.)

The following information is to be given in all Cases of vessels dealt with under Paras. 11, 12 (under 15 feet Moulded depth) and under Shelter Deck Rules.
 What is the thickness of the Bridge Sheerstrake? _____ Strake between Main and Bridge Sheerstrakes? _____

Delete the words { The Crew are, are not, berthed in the bridge house.
 that do not apply { The arrangements to enable them to get backwards and forwards from their quarters are, are not satisfactory.

Length of Bulwarks in well _____

Area of Freeing Ports required by Para. 11 (e) each side of vessel	=	Sq. ft.
Ft. Tenth. Ft. Tenth. No.	} Freeing Ports (each side of vessel)	= Sq. ft.
x x x		
x x x	} Total deficiency or excess	= Sq. ft.
x x x		



Show hereon line of Floors or Tank Top with position of any Breaks in same; also height of Peak Tank tops, &c., &c.

State any special features in the construction of the Vessel _____

Builder's name and yard number _____

Names of sister vessels _____

Owners _____

Address _____

Fee £ _____

Received by me _____

Will be charged on completion.



© 2021

Lloyd's Register Foundation