

"FU SHING".

IT IS SUBMITTED that before this case receives consideration the Danzig Surveyor be informed that although the boilers were approved for a working pressure of 245 lb. per sq. inch, the shafting was approved for only 225 lb. The shafting does not meet the requirements of the Rules for a pressure of 245 lb. per sq. inch, and the Surveyor should therefore make arrangements for the safety valves to be re-adjusted accordingly.

The Surveyors should also be informed that it is noted that a deviation of 5 degrees has been observed on the standard compass and 3 degrees on the steering compass due to the effect of switching on and off the electric circuits in the vicinity of these instruments. These deviations are excessive and steps should be taken to discover the source of the interference and to remedy it.

ad
24
9th February, 1939.

Lr 10/2

Row



© 2021

Lloyd's Register
Foundation

015405-015416-0112