

COPY

LLOYD'S REGISTER OF SHIPPING

Main Air Receivers.

No. 58/744

Port

H a m b u r g ,

21st February, 1958.

This is to Certify that

E. A s s e n

the undersigned Surveyor to this Society did at the request of Messrs, Maschinenfabrik Augsburg-Würzburg A.G. attend their works at Hamburg on the 4th December, 1958 and subsequently for the purpose of examining and testing air receivers, made to the order of Messrs. Aktiebolaget Gävle Varv, Sweden, and intended for their Yard No. 99, Engine Nos. 405211-212.

Three - Air Receivers, Works Nos. 19631, 19632, 19633, of 1000 ltrs. capacity each, fabricated by electric welding process, having an overall length of 2460 mm, 768 mm internal diameter, 16 mm thickness of shell plates, a tensile strength of 41-47 kg/mm², have been examined during all stages of construction and were made in accordance with the approved plan No. M.464576 and the Society's Rules and Regulations for Class 2 welded pressure vessels.

The material used in the construction was made at approved steelworks and tested at this works by Surveyors to this Society. The workmanship is good.

The completed air receivers have been subjected to a hydraulic pressure test of 49 kg/cm² and all found sound and tight at this pressure.

For identification purposes the receivers have been stamped:-

Nos. 744 A-B-C
LLOYD'S TEST HAM
49 kg/cm²
W.P. 30 kg/cm²
21.2.58 E.A.

Surveyor to Lloyd's Register
of Shipping.

icate is issued upon the terms of the Rules and Regulations of the Society, which provide that:-

the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly
is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances
to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any
Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of
tees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."