

(LLOYD'S REGISTER.)**VESSELS OF 100 TONS AND UPWARDS.**

o. of To

318.84

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of Shipping.

al Letters (if any) V D Z J

82.20

Official Number.	Name of Ship.	No., Date, and Port of Registry.
74808	MOUNT ROYAL PARK	37 - 1943 Montreal.

Date, and Port of previous Registry (if any). **First Registry**

5.18

6.22

the Upper

Whether British or Foreign Built.	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.	
British	Steam Screw	Victoria B.C.	1943	Victoria Machinery Depot Co.Ltd., Victoria, B.C.	
Number of Decks	...two	Length from fore part of stem, to the fore side of the head of the stem-post Rudder. stock	424	Feet.	Tenths.
Number of Masts	...two	Main breadth to outside of plank	57		6
Rigged	...not	Depth in hold from tonnage deck to ceiling amidships	34		2
Mast Raked	...Raked	Depth in hold from upper deck to ceiling amidships, in the case of three decks and upwards	-		9
Whether Cruiser	...Cruiser	Depth from top of deck at side amidships to bottom of keel...	37		-
Whether In & Out	...In & Out	Round of beam	1		5
Framework and description of vessel	...Steel Oil Tanker	Length of engine room, if any	50		2
Number of Bulkheads	...13				0

Particulars of propelling Engines, etc. (if any), and Water Ballast Tanks, as supplied by Builders, Owners, or Engine Makers.

Particulars of Propelling Engines								
No. of Engines	Description of Engines	Whether British or Foreign Made	When made	Name and address of makers	Reciprocating Engines		Rotary Engines	N.H.P. B.H.P. I.H.P. Estimated Speed of Ship
					No. and Diameter of Cylinders in each set	Length of Stroke	No. of Cylinders in each set	
1	Reciprocating Triple Expansion	Engines British	Engines 1943	Engines Dominion Engineering Co., Ltd., Montreal, Que.	3 24½" 37" 70"	48"		N.H.P. 229 I.H.P. 2500
2	Particulars of Boilers Description..... Water Tube Number..... two Iron or Steel..... Steel Loaded Pressure..... 220	Boilers British	Boilers 1943	Boilers Vancouver Iron Works, Ltd., Vancouver, B.C.				10-11 Knots

Number of water ballast tanks, and their capacity in tons: — 13 - 1523 tons

015433-015441-0157

[P.T.O.]

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of
Under Tonnage Deck	6749.57	On account of space required for propelling power	2306.
Space or spaces between Decks		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from Goods or Stores of every kind not being the personal property of the Crew.	
Turret or Trunk	10.50		
Forecastle			
Bridge space			
Poop or Break			
Side Houses	78.99	These spaces are the following, viz.:—	382
Deck Houses	221.09	Deck Houses	230.62
Chart House	11.58	Between Decks Aft	151.58
Spaces for Machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894	76.00	(Number of Seamen or Apprentices for whom accommodation is certified 54)	
Excess of Hatchways	59.16	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
		Cubic Meters.	
Gross Tonnage	7206.89	Master's Accommodation	22.39
Deductions, as per contra	2972.83	Wireless space	17.25
Register Tonnage	4234.06	Chart Room	11.58
		Steering Machinery	13.16
		Boatswains Stores	22.01
		Pump spaces	64.88
		Water Ballast in Peaks	93.12
		Total	2972.

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 861.05 tons, and the tonnage of the total spaces framed in above the Deck for propelling machinery and for light and air is 90.23 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage...

Wheelhouse 12.35 Galley 15.00 Pump Houses 6.71 Crews W.C.'s 7.28

Light & Air 14.23

Name of Master

Certificate of { Service No.
Competency No.

No. of Owners

Name, Residence, and Description of Managing Owner if there are more owners than one.

His Majesty the King in the right of Canada represented by the Honourable the Minister of Munitions and Supply of the Dominion of Canada for the time being, Ottawa, Ont. Sixty-four (64) shares.

Park Steamship Company Limited, 410, St. Nicholas Street, Montreal, Que.

Designated Managers.

Dated Montreal September 13th 1943.