

REPORT of SURVEY for REPAIRS, &c.

No. 4449

NOV 14 1892

Date of writing Report Nov 12 1892 When handed in at Local Office Nov 12 1892 Port of Aberdeen

No. in Reg. Book 45 Survey held at Aberdeen Date, First Survey Oct 29 Last Survey Nov 11 1892

on the "Saint Blair" (No. of Visits 4) Master O. Lutherland

TONNAGE: Built at Glasgow By whom Randolph Elder & Co When 1868 - 2

GROSS 564 Owners: Hoff, Kirk & Shet. S. A. Coy Port belonging to Aberdeen

UNDER DEK 484 Owners' Address (if not already recorded in Appendix to Register Book.)

NET 300 Surveyed Afloat or in Dry Dock? Name of Dock Aberdeen

Destined Voyage coasting

WB=Decks tons; f tons; uE&B tons; CellDB tons; FPT tons; APT tons; MT tons.

Particulars of Classification (which must be inserted precisely as in Register Book & Supplements).

CHARACTER. * for Special Survey. Date of last Survey and of Periodical Surveys. Years Assigned how expired. Machinery and Boiler Surveys (including date of N.B., if any).

8 8 A 1. 1091 8 8 Lth No 3. 285 8 8 Abn No 1-89

8 8 Lth No 3. 285 8 8 Abn No 1-89

8 8 Abn No 1-89

Society's Freeboard (if assigned) as 1 ft 11 1/2 ins. painted on Ship and now verified

REPAIRS, OR EXAMINATION AS PER RULE, FOR Annual Survey

The vessel placed in the above dry dock, the bottom examined and found in good condition and afterwards repainted.

The shoe on the forefoot considerably worn has now been renewed.

The 2nd heavier anchor missing and 30 fathoms of chain cable.

These have now been supplied.

Height of anchor & stock 16-3-0 Footman's. No of certificate 13384

" " Stock 3-8-21 Makers. J. Abbot & Co

Press strain 14 tons 3-0-14. Mark 3. 92. Tested at Low Walker

G. C. Perrins Supert Nov. 2. 1892. Height Required by the Rules 13 1/2 cwt

30 fathoms 1 1/2 chain cable height 24-7-18. Making strain 42 1/2 tons

Lower strain 28 1/2 tons Makers John Abbot & Co. No of certificate 6610

Tested at Low Walker Oct 22/92. G. C. Perrins Supert. Size req^d by Rules 1 1/2

SUMMARY OF DAMAGE REPAIRS: — Plates, Faird or Repaired; Frames, ditto. Plates, Renewed; Frames, ditto. Other Repairs.

PRESENT CONDITION OF THE

Decks Good Transoms, Pointers, & Crutches Good Copper, or Y.M. Good Hatches Good

Waterways " Timbers of Frame at the openings " When put on, Month Year Boats "

Coamings " Ditto ditto at other places " Rudder Good Masts, Yards, &c. "

Up'r Dk. Beams & Fastenings " Keelsons " Windlass & Capstan " Condition, how ascertained from

Low'r Dk. Beams & Fastenings " Clamps, Shells & Stringers " Pumps " Sails "

Plating " Ceiling " Engine Room Skylights " Anchors No. of 3131824

Planking " Cement or Asphalt (State which) " Coal Bunker, Open'gs, Lids, &c. " Cables, length 210 f size 1 1/2

Treenails or Rivets " Tanks (State if now tested) " Scuppers " (State if now ranged yes

Breasthooks & Stems " Caulking of Bot'm, D'k, & Wat'rw'ys " Cargo & Main H'tch'w'ys " Standing & Running Rigging "

General Observations, Opinion as to Class, Recommendation, &c.:

State clearly whether any and, if so, what alteration is suggested to be made in the existing classification and notification of the vessel in the Register Book consequent upon this survey, thus, for example:—"to remain as now classed in the Register Book without fresh record of Survey," "to remain as classed and to have record of survey, 9,91," or "to remain as classed and to have record of survey, 9,91, and the notations of ss No. 1-91 and ptND91, &c."

This vessel so far as seen is in good and efficient condition

and eligible in my opinion to remain as classed and

to be noted 11. 92 in the Register Book.

Office Fee (if chargeable) per Scale II., Sec. 27 £ : : Fees applied for,

Survey Fee (per Section 28) £ : : 18

Special Damage or Repair Fee (if any) £ : : Received by me,

(per Sec. 28.) £ : : 18

Travelling Expenses (if chargeable) £ : :

Second Surveyor's Fee (if any) £ : :

*Is Certificate now required?

Committee's Minute

Character assigned

TUES, 15 NOV 1892

ABN 11, 92

Surveyor to Lloyd's Register of British & Foreign Shipping.

© 2019

Lloyd's Register

Foundation

ABN 11-0073