

REPORT of SURVEY for REPAIRS.

No. 1303 Survey held at Aberdeen Date 16 Aug^t 1848
 on the Barque Warrior Master J. Stafford
 Tonnage 301 Built at Dundee When built 1837
 By whom built _____ Owners W. Duthie
 Port belonging to Aberdeen Destined Voyage Port-Philip
 If Surveyed Afloat or in Dry Dock on Slip & afloat

Last Survey, No. in Clyde-1845 N^o 45 Reg^d B. 1848 Classed Res^d 44-5A1
 Port 1723 Clyde

REPAIRS

Renewed on Larboard side Lower half of Quarter Timber with B^h O^k 5 Short shifts in Bends & Topsides (wake of Quarter timber) with Dantzic O^k 4 of the Counter plank with do. same side also one Shift in Bends with Dantzic Oak in way of Lower deck Binding with the fastenings passing through the same. On Starboard side one Shift in Lower Street of Bends of Dantzic Oak & the fastening of Lower deck in same. Also several pieces of the bends in way of Butts on both sides all with foreign oak 4 pair Diagonal Iron Knees applied to Midship Hold Beams New Windlass & Mudlass spindles Metal Sheathing stripped & the bottom dubbed thereafter caulked from Keel to top of Bends & sheathed with Yellow Metal 26 24 & 22 oz over paper to 13 1/2 ft forward & aft

Present Condition of the

Decks <u>Good</u>	Treenails <u>Good</u>	Windlass and Capstan <u>new with Winch Good</u>
Waterways <u>go</u>	Breasthooks and Stemson <u>go</u>	Pumps <u>2 Good</u>
Comings <u>go</u>	Transoms, Pointers, and Crutches <u>go</u>	Boats <u>3 go</u>
Upper Deck Beams & Fastenings <u>Good & firm</u>	Timbers of the Frame <u>Fair</u>	Masts, Yards, &c. <u>Complete & Good</u>
Lower Deck Beams & Fastenings <u>Good & new firm</u>	Keelsons <u>Good</u>	Sails <u>Two full sets (one new)</u>
Planksheers	Clamps and Shelves <u>go</u>	Anchors No. of <u>3 B^h 1 S^h 2 good order</u>
Sheerstrakes	Ceiling <u>go</u>	Cables <u>Complete & Good</u>
Topsides	Rudder <u>go</u>	Hawsers and Warps <u>1 S^h Haw 1 S^h War 3 Warps</u>
Wales	Copper <u>New</u>	Standing & Running Rigging <u>good & Complete</u>
Plank (Bottom) and Counter <u>Good</u>		

General Observations and Opinion,

I Have carefully surveyed this vessel. & found her as noted - sheer & form unaltered eligible to carry dry & perishable cargoes to & from all parts & may remain as classed.

The Amount of Fee. for Rep^s.....£ 2 : 0 : 0 is received by me,

Certificate (if required) :

Committee's Minute

25th Aug 1848

Character assigned

Res^d 5 A

Thomas Alexander



© 2021

Lloyd's Register Foundation