

Steel screw steamer "CHANTICLEER", No. 614 in R.B., Built at Hull in 1894, and classed 100A1 "Steam Trawler."

It is proposed to lengthen this vessel by 11'. 8" amidships, and sketches shewing this alteration are submitted by Mr. Fowell.

Rule dimensions ; 112.9 x 20.75 x 12.25

Scantling numbers ; 40.49 and 4571

Proportions ; Length = 5.4 Breadths = 9.2 Depths.

The scantlings of this vessel as built were in excess of the Rule requirements, and, with the proposed lengthening, still meet the requirements of the Rules.

It is submitted that provided the equipment be as indicated on the plan ; the scantlings of the new materials be equivalent to those originally fitted in the vessel, and the alterations as shewn be carried out to the Surveyor's satisfaction, the same will merit approval.

Lr. 16. 2. 06
Ans. M.H.W.
2 plans