

## S.S. Armada

It is submitted That provided The present diameters of the shafting are the same as those given in the Entry report viz crankshaft 10" dia, Tunnel shafts 9 1/4" dia & cross shaft 11" dia, The proposal to fit to triple the main engines by fitting a High pressure Cylinder 19" diameter above the present A P Cylinder (which is 29" dia), & to increase the working pressure to 160 lbs per square inch merits approval.

The two main Boilers salvaged from the S.S. 'Adorna' will require to be carefully examined & their working pressure, which was originally 160 lbs, must be determined by their present condition.

The Aberdeen Surveyors should be requested to ascertain whether the new Owners desire to have the refrigerating machinery certified by this Society

A R R

10.3.13

Lt: - 11/3/13

J. M.



© 2019

Lloyd's Register  
Foundation

ABN52-0137