

# REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No. 2458** Survey held at Aberdeen Date May 18<sup>th</sup> 1859  
191 on the Agnes Do Master A. M. Mac  
Tonnage 199 Built at Aberdeen When built 1856  
By whom built Duffie Owners James C. Suttar  
Port belonging to Aberdeen Destined Voyage India  
If Surveyed Afloat or in Dry Dock On Duffie in Tartan off afloat

Last Survey, No. 2205 Port Aberdeen Classed 2<sup>nd</sup> class exposed

**REPAIRS** The vessel placed on a potant slip, and scraped right from the light water mark upwards, including planstee and waterways, treenails and bolts of iron driven out in accordance with the Rules, treenails found to be good, but the iron bolts some what corroded. The Hold, timbers and gunwales cleared, the windlass embury, the wood linings stripped, found to be in good condition, and all requirements of the Rules fully complied with. Renewed the through bolts of iron in the Head beam bridging 24 1/2 diameter, the treenails driven out for survey, 18 Hanks of ceiling in Head of Pitch Pine and English Oak, 3" thick, the ceiling remailed where necessary. A Pair of Santa Nelsons now fitted of Greenheart 11x12, 40 lbs. fastened with yellow metal bolts 1 1/2 diameter. The vessel now re-matched over all, and the bottom sheathed with yellow metal in felt to G. S. water line.

Present Condition of the		
Decks	Good where seen.	Treenails Good where seen
Waterways	"	Breasthooks and Stenson "
Comings	"	Transoms, Pointers, and Crutches "
Upper Deck Beams & Fastenings	"	Timbers of the Frame at the openings "
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places "
Stanksheers	"	Keelsons "
Deerstrakes	"	Clamps and Shelves "
Sides	"	Ceiling "
Stanchions	"	Rudder "
Plating (Bottom) and Counter "	"	Copper <u>Yellow Metal</u> When put on <u>Now</u>

General Observations and Opinion, Caulking of Bottom, Deck, & Waterways. Good where tested  
This vessel appears to be in good and efficient condition and eligible in our opinion to be classed A in Third from 1858. The requirements of the Rules for fast new way for it in Third being now fully complied with.

Amount of Fee... £ 20. 0 is received by me,  
Classing fee 2. 0 0  
Special... 2. 2 0  
Change of Owners 10. 0  
Certificate (if required) : 2. 6

Committee's Minute 21<sup>st</sup> May 1859  
Character assigned A in Third  
record repair  
J. W. Little  
John Miller Freeman  
Lloyd's Register  
FABNS 0331