

Report of Survey for Repairs of Engines and Boilers.

(Received at London Office, RECEIVED 27th FEB. 82.)

No. 127

No. in Reg. Book. Survey held at Aberdeen Date, first Survey 10th July Last Survey 18th July 1882

30+ on the Machinery of the I.S.S "Ballater" (Number of Visits 2)

Tonnage, Gross <u>741.</u>	Built at <u>Aberdeen</u>	When built <u>1876</u>
Ditto, Net <u>471.</u>	Owners <u>J & A Davidson</u>	Port belonging to <u>Aberdeen</u>
Diameter of Cylinder <u>32 1/2 x 45</u>	Engines made by <u>Hall Russell & Co</u>	When made <u>1876</u>
Length of Stroke <u>30"</u>	Boilers made by <u>Do Do</u>	When made <u>1876</u>
Pressure of Steam <u>62 lbs</u>	If Surveyed Afloat or in Dry Dock <u>afloat</u>	Classed <u>100 A.1.</u>
Registered Horse Power <u>90</u>	(State name of Dock.)	Years assigned <u>7.80</u>
Last Survey No. _____	Port _____	Character in Register Book. _____

Particulars of Repairs and Examination of Engines and Boiler while

(State cause of Repairs.)

undergoing repairs.

Boiler. The boiler has been retubed at this time, and two new renew stays fitted in back of combustion chamber, and 12 rivets renewed round bottom seam at front of boiler. otherwise the boiler is in good condition.

Donkey boiler cleaned out and in good order.


Engines The engines have been opened out, and examined, cylinders, valves, pumps, crank and tunnel shafting and bilge piping; the Condenser opened out & cleaned, and new tubes fitted at this time. the high pressure piston rod and valve spindles turned up and new neck brasses fitted, new packing ring fitted in low pressure piston, all the brasses have been readjusted and pump valves examined, and all is now in good working condition.

General Observations, Opinion, and Recommendation:— The boiler and machinery of this vessel having received a thorough overhaul at this time, which in my opinion places them in good safe working condition and eligible to remain as entered into the Register Book B & F.S. 18/2/82.

Entry or Registering Fee... £ : :
 Survey Fee (per Section 27) ... £ 1 : :
 Certificate (if required) ... £ : :
 Travelling Expenses, if any, £ 1-15-6

received by me, John Stunoch
 25th 1882
 Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.
 Dundee District

Committee's Minute
 Assigned



Insert Character precisely as in the Register Book.

3388 Alton

His sub number that has correct is slight
to have the notifications BS 2, 52
re corded subject to the boiler being
re surveyed in 12 months as per
rule

As should not be recorded
until report has been
received that sea
connections to have
been examined

[Handwritten signature]



© 2019

Lloyd's Register
Foundation

Report of Survey for Repairs of Engines and Boilers