

# Report of Survey for Repairs, &c., of Engines & Boilers.

(Received at London Office,

THURS 10 APRIL 1885

No. 4992

No. in Survey held at

Aberdeen

Date, first Survey

28/2/85

Last Survey 31<sup>st</sup> March 1885

Reg. Book.

287 on the Machinery of the

S.S. Benaman

(Number of Visits

Year Month

Tonnage, Gross

381

Built at

Aberdeen

When built

1878

Ditto, Net

247

Owners

Davidson S.S. Coy (Lim.)

Port belonging to

Aberdeen

Diameter of Cylinder

19 3/4

Engines made by

Hall, Russell & Co

When made

1878

Length of Stroke

22

Boilers made by

Do

When made

1878

Pressure of Steam

62 lbs

If Surveyed Afloat or in Dry Dock

(State Name of Dock.)

Classed

100 A 1

Registered Horse Power

431 1/2

Last Survey No.

Port Abu.

S.S. Abu. No 1. 82

## Particulars of Repairs and Examination

Boiler Survey

(State clearly the cause of Repairs if any, and in detail, the nature and extent of Examinations and subsequent Repairs. Repairs on account of Damage should be separated from Repairs due to other causes. State also the dates and initials of any letters respecting this case.)

How done viz: - Main boiler opened up, and examined. All tubes out and renewed. Patch fitted on front plate below centre furnace, and the boiler put in good condition.

Donkey boiler cleaned out, examined, and found in good

The machinery generally overhauled and repaired.

Vessel placed on A.Hall & Co patent ship, and outside fixing of sea cocks, valves. Screw shaft drawn in and stem bush relined with wood, and new propeller fitted. all in good order.

## General Observations, Opinion, and Recommendation:--

(State clearly what alteration, if any, is suggested to be made in the existing notification of the vessel's machinery in the Register Book, consequent upon this survey.)

The machinery of this vessel is now in good Condition and eligible in our opinion to remain as Classed and marked B.S. 3-85

Office or Registration Fee (per Sec. 27)

£

Survey Fee (per Section 28)

£

Special Damage Fee (per Section 28)

£

\*Certificate (if required)

£

Travelling Expenses (if chargeable)

£

2 : 8 : 6

received by me,

15 April 1885

W. Darling & J. Sturrock  
Engineer Surveyor to Lloyd's Register of British and Foreign Shipping.  
Dundee District

Committee's Minute

Assigned

TUESDAY 21 APRIL 1885

B.S. 3-85



Lloyd's Register  
Foundation

ABNS-0142

3590. HBN.

It is submitted that this vessel is  
eligible to have the certification  
P.S. 3.8.5 recorded the boilers  
being subject to survey as  
particular.

D.P.

16/4/85.



© 2019

Lloyd's Register  
Foundation