

4

Dutch Barque "Professor van der Boon Mesch"
632 Tons built at Amsterdam in 1864

This vessel is built of continental oak
8 years material, and salted as customary
in Holland, and as admitted by the Committee
for additional year. She has been specially
surveyed at Amsterdam and is
recommended for the 6 A. 1. Class or
Rest^d 5 years A. 1.

It is submitted that the Rule for
Restoration Sec 56 has not been fully
complied with; the shales of ceiling in
the range of the first futtock heads not
having been removed. She appears
however eligible to be classed

8 years under Table A

1 year for salt

9 A - Continued A for 6 years from
Nov. 1873.

The anchors are in excess of the Rules.
The chain cables are 105 fms $1\frac{11}{16}$ "

105 - $1\frac{12}{16}$ "

and 105 - $1\frac{2}{16}$ "

the rule requiring 240 fms of $1\frac{8}{16}$ ".

Her eligibility to the Figure 1 is
respectfully submitted to the favorable
consideration of the Committee.

1873

J. N.
25/
11/77



© 2018

Lloyd's Register
Foundation