



No. **4392**

TESTS OF BOILER STEEL.

Tests of **23** Steel **Plates** manufactured by **The Steel Co. of Scotland** of **Glasgow**
 for Boiler No. **28** to be constructed by **Messrs McEwan Lewis** of **Belfast**
 for **Titanic Bel. res 3422**

Date first visit _____ last visit _____ No. of visits _____

The _____ specified in the accompanying copy of Advice Notes were rolled from _____ charges. The tensile test has been applied to **8** samples as set forth below, and the temper and bending tests **Satisfactory**

When a second test is applied, the result should be recorded immediately below the record of the original test. The number of plates or bars included in a rejection must be clearly stated.

No.	Purpose.	Charge Mark.	No. of plates or bars in same charge	Mark on plate and test piece.	Dimensions.			Ultimate Stress.		Exten. in 8 ins. %	Remarks.
					Thickn.	Brdth.	Area.	Total.	Sq. Inch.		
					Ins.	Ins.	Ins.	Tons.	Tons.		
	15'-0" x 10' x 1 5/16" Shell	0.71	6405	.95	1.34	1.273	36	28.2	25		
A.76		9091	1.19	1.14	1.357	37.2	27.4	27.5			
	Front Shell	L.74	9093	1.2	1.14	1.368	39.6	28.9	23		
J.64		9117	.95	1.14	1.083	29.35	27.1	24.5			
	Comb'n Shell	A.78	9132	1.2	1.15	1.38	40.05	29	24.5		
L.77		9162	1.19	1.15	1.368	39.15	28.6	25			
	Shell	G.66	4152	.565	1.13	.638	18.4	28.8	22.5		
0.78		9209	1.2	1.11	1.332	36.05	27	27.5			

BP 1/4/07

Fee £ : :
 Expenses £ : :
 £ : :

To be paid by _____



J. J. Roberts
 Surveyor, Lloyd's Register,

Glasgow
 29/3/07

Mr. Hwaine Lewis'
No. 28 Bm

LESLIE OF BOITHEE STREET

STONES RECORDED OF BRITISH AND FOREIGN ARCHIVES



© 2019

Lloyd's Register
Foundation