

The words FORGINGS or CASTINGS, IRON or STEEL, should be struck out as may be required.

Received at Belfast Office, June 3<sup>rd</sup> 1888

# Lloyd's Register of British and Foreign Shipping.

(Report on Vessel No. 213 Port Belfast)

## No. 1618 SHIP FORGINGS OR CASTINGS.

I have to report that the undermentioned Iron or Steel ~~Forgings or~~ Castings, manufactured by The Steel Coy of Scotland of Newton for the Vessel No. 213, being built by Messrs Harland & Wolff of Belfast have been inspected by me as set forth below, and found to be, so far as can be seen, a sound casting, and free from surface defects.

Mark on Forgings.

Lloyd's  
No. MS.

W. Sibson  
Glasgow.

	STERN FRAME.	RUDDER FRAME.	STEM.
Material* . . . .	<u>Siemens' Martin Steel</u>	/	/
How made . . . .	<u>Cast, and annealed</u>		
Dimensions . . . .	<u>For 10x6. Off 10 1/2 x 6"</u>		
Progress on Inspection . . . .	<u>Completed.</u>		
Dates when Inspected	<u>April 27<sup>th</sup></u> <u>May 12<sup>th</sup></u>		

SKETCHES OF FRAMES SHEWING POSITION AND DESCRIPTION OF WELDS OF FORGINGS, OR PARTICULARS OF TESTS APPLIED TO CASTINGS.

This frame was raised to an angle of 45° & allowed to drop suddenly on a hard and level floor, it was afterwards raised clear of the ground and hammered all over to test its soundness, & after careful examination, in which no surface defects were observed, was passed as satisfactory

\* If of Iron, state whether scrap or puddled iron.

Harland & Wolffs. 213.

Stern Frame.

S. L. Lord Londonderry

Belfast Report

No 3510



© 2019

Lloyd's Register  
Foundation