

Form A.

Certificate of Approval of the position (Alteration of the position) of the Centre of the Disc, and of the Lines to be used in connection therewith, in pursuance of the Merchant Shipping Act, 1894.

# Lloyd's Register of British & Foreign Shipping.

ESTABLISHED 1834.

No. 61629  
3215

No. 2, White Lion Court, Cornhill,

London 3<sup>rd</sup> February 1899.

This is to Certify that the Committee of this Society have approved, on behalf of the Board of Trade, the position (or alteration of the position) of the centre of the disc and of the lines to be used in connection therewith on the Steamship "Memnon"

Official No. 98125, and hereby certify—

- (a.) That the centre of such disc is placed at six feet three & a half inches below the upper deck line marked under the provisions of the Merchant Shipping Act, 1894.
- (b.) That the position of the lines to be used in connection with the disc shall be as follows and as shown in the subjoined diagram:—

Maximum load-line in fresh water.—The upper edge of this line is ✓ five & a half inches above the upper edge of the horizontal line passing through the centre of the disc.

Maximum load-line in Indian summer.—The upper edge of this line is ✓ four & a half inches above the upper edge of the horizontal line passing through the centre of the disc.

Maximum load-line in summer.—The upper edge of this line is on the same level as the upper edge of the horizontal line passing through the centre of the disc.

Maximum load-line in winter.—The upper edge of this line is ✓ four & a half inches below the upper edge of the horizontal line passing through the centre of the disc.


~~Maximum load-line in winter, North Atlantic.—The upper edge of this line is ✓ four & a half inches below the upper edge of the horizontal line passing through the centre of the disc.~~

Top of statutory deck line above the top of wood or iron deck at side one & a quarter inches.

This Certificate is to remain in force only so long as the vessel remains in her present class, provided that no change has taken place in the structural condition of those deck erections in respect of which deductions have been made for freeboard.

NOTE.—In accordance with the Regulations made by the Board of Trade, the disc and lines must be permanently marked by centre punch marks or cutting, and the particulars given in this Certificate are to be entered in the official log. This Certificate must also be framed and put up in some conspicuous part of the ship.

If and so soon as the class of the ship is either changed or withdrawn, or if and so soon as any change is made in the structural condition of the deck erections above mentioned, this Certificate will be cancelled and must be delivered to the Committee of Lloyd's Register for that purpose, and the owner must then apply for a new Certificate.



Witness my hand,

*A. J. Dykhouse*  
Secretary.

*Edward Street*  
Deputy Chairman.



*Cancelled*  
*New Certificate issued*

The Freeboards given in this Certificate are not intended to apply to vessels when navigating inland waters or rivers, and when a stretch of such water has to be traversed such deeper loading will be permissible as may be due to the weight of fuel required for consumption between the points of departure and the open sea.

BE0057-0081

[R.T.O.]



The *Summer freeboard* applies to voyages from European and Mediterranean ports, from April to September inclusive. In other parts of the world this freeboard should be used during the corresponding or recognised summer months.

~~The *freeboard for Winter North Atlantic trades* applies to vessels when entering the North Atlantic, when sailing to, or from, the Mediterranean, or any British or European port, and which may sail to, or from, or call at, ports in British North America, or Eastern ports in the United States, north of Cape Hatteras, from October to March inclusive.~~

The *freeboard for Indian Summer* applies to voyages in the fine season in the Indian Seas between the limits of Suez and Singapore.



© 2019

Lloyd's Register  
Foundation