

SS No 76

Freeboard Rpt No 2463

"Evelien"

Rel 3872

BEL58-101

Handwritten notes in pencil, mostly illegible due to fading and bleed-through.



WED 26 MAR 90

Midship Section No 76. S.S. "Everdeen" 13c. Rep't 3872.
To Class 100. A1:
Dimensions. 171'-0" x 26'-0" x 12'-1" (to floors.)
Scale 1/2" = one foot.

Numerals. 1/2 Girth. 23.58. Proportions Breadths. 6.5.
1/2 Breadth. 13. Depths. 12.8.
Depth. 13.35
49.73 x 170. = 8471. Plating No.
787.
9293 9258 Equipment No. 5 1/2 x 3 x 7/16

Equipment	
2 Bower anchors ex Stock	12 lots each. 12 supplied.
1 " " " "	8 1/2 " "
1 Stream " " "	3 1/2 " "
1 Hedge " " "	1 1/2 " "
1 " " " "	3/4 " "
195 Fathoms 1 1/2 Stud Chain Cable.	
60 " 2 1/2 Steel wire.	
75 " 8 Towline.	
90 " 6 Warpr.	



Note: - Scantlings written in blue refer to lower

Heel pieces at centre as per Rule or vertical angle fitted as amended.

Amendments in this ink are as fitted. M.

This C.B.D. extends from fore head of E413 space to after peak 13' head which includes midships.

